

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I 000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I 000					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	50	50					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	108.9	108.9					
25200110	SODDING, SALT TOLERANT	SO YD	50	50					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6720	6720					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7	7					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	275	275					
40600300	AGGREGATE (PRIME COAT)	TON	35	35					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	235	235					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	13	13					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	50	50					
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	350	350					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	113	113					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	12	12					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	122	122					* 81400115	HANDHOLE TO BE ADJUSTED	EACH	1	1					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	710	710					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	148	148					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	8450	8450					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	300	300														
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	600	600														
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	172	172														
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	129	129														
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	129	129														
50300300	PROTECTIVE COAT	SO YD	380	380														
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	2	2														
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1														
67100100	MOBILIZATION	L SUM	1	1														
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1														
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1														
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1														
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1705	1705														
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	108.9	108.9														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6720	6720														
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	275	275														
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	235	235														
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	50	50														

*Specialty Items