



COORDINATE DATA			
STATION	NORTHING	EASTING	REMARKS
400+48.08	1,800,300.04	1,046,374.19	POT IL. RTE. 56
400+52.69	1,880,300.14	1,046,378.80	POT IL. RTE. 56 (STA. 11024+06.82 NAPERVILLE RD)
410+16.56	1,880,321.77	1,047,342.43	PC CURVE 8 IL. RTE. 56
426+48.89	1,880,412.27	1,048,971.95	PT CURVE 8 IL. RTE. 56
11004+00.00	1,878,451.83	1,045,599.30	POT NAPERVILLE RD
11008+11.65	1,878,839.42	1,045,737.96	
11012+04.31	1,879,201.20	1,045,890.59	POT NAPERVILLE RD
11024+04.41	1,880,297.94	1,046,377.82	POT NAPERVILLE RD
11024+06.82	1,880,300.14	1,046,378.80	POT NAPERVILLE RD (STA. 400+52.69 IL. RTE. 56)
11032+03.69	1,881,028.34	1,046,702.44	POT NAPERVILLE RD
11041+86.54	1,881,923.93	1,047,107.28	PC CURVE 1 NAPERVILLE RD
11048+27.68	1,882,508.16	1,047,371.37	PI CURVE 1 NAPERVILLE RD
11054+48.89	1,883,149.30	1,047,374.02	PT CURVE 1 NAPERVILLE RD

CURVE DATA											
CURVE	P.I. STATION	Δ	D	T	L	R	E	PC STATION	PT STATION	M	CHORD
IL. RTE. 56 CURVE 8	418+33.03	3° 47' 11" (LT)	0° 13' 55"	816.46'	1,632.33'	24,700.40'	13.49'	410+16.56	426+48.89	13.48'	1,632.03'

FILE NAME =	DESIGNED - JMM	REVISED -
...ADV_0162419-shr-ABT3.dgn	DRAWN - TMB	REVISED -
USER NAME = tbenk	CHECKED - RMT	REVISED -
PLOT DATE - 2/25/2010	DATE - 2/25/2010	REVISED -

benesch

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

ALIGNMENT PLAN

SCALE: 1"=250' SHEET NO. 3 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(57, 58 & 59)-1	DUPAGE	58	13
CONTRACT NO. 60K47				
ILLINOIS FED. AID PROJECT				