

SPECIALTY ITEMS SPECIAL PROVISION	PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNITS	TOTAL QUANTITY	KEYES AVENUE QUANTITY	INDUSTRIAL DRIVE QUANTITY	MILL AVENUE QUANTITY	80% FEDERAL, 20% VILLAGE			100% VILLAGE
								1000	Y002 - TRAFFIC SIGNS	Y003 - LANDSCAPING	
X Δ	X0326713	SANITARY SEWER CONNECTION	EACH	2	2	0	0	2			
X Δ	X0539200	DROP MANHOLE CONNECTION	EACH	2	2	0	0	2			
X Δ	X0839900	SANITARY SEWER REMOVAL 6"	FOOT	580	580	0	0	580			
X Δ	X0840000	SANITARY SEWER REMOVAL 8"	FOOT	1,396	1,396	0	0	1,396			
Δ	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	5	5	0	0	5			
Δ	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	20	20	0	0	20			
Δ	X4023000	TEMPORARY ACCESS (ROAD)	EACH	6	6	0	0	6			
X Δ	X5630706	CONNECTION TO EXISTING WATER MAIN 6"	EACH	1	1	0	0				1
X Δ	X5630710	CONNECTION TO EXISTING WATER MAIN 10"	EACH	10	10	0	0				10
X Δ	X5640150	FIRE HYDRANT ASSEMBLY COMPLETE	EACH	8	8	0	0				8
Δ	XX000610	RELOCATE EXISTING MAILBOX	EACH	4	4	0	0	4			
X Δ	XX000836	PRESSURE TESTING AND DISINFECTION	L SUM	1	1	0	0				1
X Δ	XX001342	DOMESTIC WATER SERVICE BOX TO BE REPLACED	EACH	5	5	0	0				5
X Δ	XX001386	SANITARY SEWERS, PVC, 8"	FOOT	851	851	0	0	851			
X Δ	XX001464	SANITARY SEWERS, PVC, 6"	FOOT	538	538	0	0	538			
X Δ	XX001465	PVC SANITARY SEWER, 10"	FOOT	415	415	0	0	415			
X Δ	XX001470	SANITARY SERVICE CONNECTION	EACH	18	18	0	0	18			
X Δ	XX001877	SUMP PUMP LINE CONNECTION	EACH	20	20	0	0	20			
X Δ	XX002136	PRESSURE CONNECTION	EACH	1	1	0	0				1
X Δ	XX002982	GATE VALVES, 6"	EACH	1	1	0	0				1
Δ	XX005043	ORNAMENTAL SIGN POST	EACH	15	6	4	5	15			
X Δ	XX006248	SANITARY SEWER, PVC D3034 8"	FOOT	521	521	0	0	521			
X Δ	XX006250	SANITARY SEWER, PVC D3034 10"	FOOT	156	156	0	0	156			
X Δ	XX006464	DOMESTIC WATER SERVICE BOX TO BE ADJUSTED (SPECIAL)	EACH	5	5	0	0				5
Δ	XX006571	REMOVE AND REPLACE BOLLARDS	EACH	1	1	0	0	1			
X Δ	XX006884	CRUSHED STONE, TRENCH FOUNDATION	CU YD	2,000	2,000	0	0				2,000
X Δ	XX011700	WATER MAIN FITTINGS	POUND	1,087	1,087	0	0				1,087
Δ	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	12,005	11,403	602	0	12,005			
Δ	Z0019600	DUST CONTROL WATERING	UNIT	15	15	0	0	15			
Δ	Z0022800	FENCE REMOVAL	FOOT	605	605	0	0	605			
X Δ	Z0057000	SANITARY SEWER 10"	FOOT	35	35	0	0				35
X Δ	Z0057300	SANITARY SEWER 18"	FOOT	110	110	0	0				110
* Δ	Z0076600	TRAINEES	HOUR	500	500	0	0	500			

\* = Y080

COPYRIGHT © 2010 ENGINEERING ENTERPRISES, INC.

FILE NAME	USER NAME = #USER#	DESIGNED - JAM, SWM	REVISED - 12/02/09
#FILE#		DRAWN - KKP	REVISED - 01/22/10
	PLOT SCALE = #SCALE#	CHECKED - JAM	REVISED - 02/03/10
	PLOT DATE = #DATE#	DATE - 10/16/09	REVISED - 02/08/10

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PROJECT NO. HPP-1468(004)	JOB NO. C-91-175-06
SCALE: N/A	SHEET NO. 5 OF 92 SHEETS
STA. N/A	TO STA. N/A

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	06-00015-00-PV	KANE	97	8
FED. ROAD DIST. NO. - [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 63406	

Plotted: February 8, 2010 @ 9:28 AM By: Kris Pung - Tab: 08-QUANTS (22x34)

Path: H:\S05\PROJ\140356\DWG\140828\DWG\_FINAL\_ENG\140356-CVR