

VALVE VAULT SCHEDULE								
STR.	STATION	OFFSET	LT./RT.	4"	8"	10"	10"	RIM ELEV.
				GATE VALVE	GATE VALVE	TAPPING VALVE	GATE VALVE	
				IN V. BOX (EACH)	IN 4' VV (EACH)	IN 5' VV (EACH)	IN 5' VV (EACH)	
1	203+16	6.5	LT	1				885.14
2	207+37	2.7	LT			1		887.58
3	213+40	24.9	LT				1	902.42
3A	212+88	21.0	RT		1			901.00
4	215+94	19.5	LT				1	906.27
5	219+39	21.3	LT				1	907.45
<b>TOTALS</b>				<b>1</b>	<b>1</b>	<b>1</b>	<b>3</b>	

SANITARY SEWER STRUCTURE SCHEDULE											
STR.	STATION	OFFSET	LT/RT	SAN MH	SAN MH	STRUCTURE INVERTS				RIM ELEV.	
				TY. A	TY. A	N	S	E	W		
				4' DIA.	5' DIA.						
				TY. 1 F, CL	TY. 1 F, CL						
				EACH	EACH						
1	201+71	17.7	RT	1							885.39
2	203+03	17.7	RT	1			879.75	879.03	879.03		884.89
3	205+86	17.7	RT	1			879.98 (6")	880.49	879.81	887.06	
4	208+70	22.0	RT	1			881.69	882.09	881.64	890.33	
5	209+54	9.50	RT	1				883.27 (6")	882.44	882.44	893.10
6	209+93	9.50	RT	1					882.60	882.60	894.11
7	213+09	9.50	RT		1	883.86	895.45	895.67	883.86	901.52	
7A	213+11	45.0	RT	1		895.60	896.05				901.30
8	213+09	10.5	LT	1		883.94	883.94				901.48
9	213+81	7.25	LT	1				895.97	895.97	903.18	
10	216+10	7.25	LT	1				896.89	896.89	906.31	
11	218+39	7.25	LT	1				898.00 (8")	898.00 (6")	897.81	906.52
<b>TOTALS</b>				<b>11</b>	<b>1</b>						

FIRE HYDRANT SCHEDULE					
STR.	STATION	OFFSET	LT./RT.	FIRE HYDRANT ASSEMBLY, COMPLETE (EACH)	BURY ELEV.
1	201+98	22.1	LT	1	889.40
2	205+76	21.5	LT	1	887.50
3	208+60	27.2	LT	1	890.60
4	211+60	28.0	LT	1	897.60
5	214+51	29.0	LT	1	904.50
6	218+24	32.0	LT	1	906.55
7	222+66	18.4	LT	1	906.80
8	212+98	54.0	RT	1	901.50
<b>TOTALS</b>				<b>8</b>	

SANITARY SEWER SCHEDULE									
PIPE #	D.S. STR.	U.S. STR.	LENGTH	SLOPE	TRENCH BACKFILL	8"	8"	10"	10"
						SDR-26	SDR-21	SDR-26	SDR-21
						(FOOT)	(FOOT)	(FOOT)	(FOOT)
SAN 1	Ex MH	1	156	0.28	285.1			156	
SAN 2	1	2	133	0.28	225.7				133
SAN 3	2	--	23	0.40	16.2	23			
SAN 4	2	3	282	0.28	551.5				282
SAN 5	3	4	287	0.40	569.1		287		
SAN 6	4	Ex MHB	35	0.89	39.3	35			
SAN 7	4	5	86	0.40	102.2	86			
SAN 8	5	6	38	0.40	58.2	38			
SAN 9	6	7	315	0.40	616.0		315		
SAN 10	7	8	20	0.40	47.0		20		
SAN 11	7	7A	35	0.43	24.2	35			
SAN 12	7	9	74	0.40	56.0	74			
SAN 13	9	10	229	0.40	223.6		229		
SAN 14	10	11	230	0.40	274.4	230			
<b>TOTAL</b>					<b>3,089</b>	<b>521</b>	<b>851</b>	<b>156</b>	<b>415</b>

Plotted: February 1, 2010 @ 2:07 PM By: Kris Pung - Tab: 14-SCHEDULES (22x34)

FILE NAME	USER NAME = #USER#	DESIGNED - JAM, SWM	REVISED - 12/02/09
#FILE#		DRAWN - KKP	REVISED - 01/22/10
	PLOT SCALE = #SCALE#	CHECKED - JAM	REVISED - 02/03/10
	PLOT DATE = #DATE#	DATE - 10/16/09	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE: N/A	PROJECT NO. HPP-1468(004)	JOB NO. C-91-175-06	
	SHEET NO. 11 OF 92 SHEETS	STA. N/A TO STA. N/A	

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	06-00015-00-PV	KANE	97	14
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT			CONTRACT NO. 63406	

PATH: \\S05PROG\HAG56\DWG\HAG56\WORK\FINAL ENO\HAG56-COR