

PAVEMENT MARKING SCHEDULE								
THERMOPLASTIC PAVEMENT MARKINGS							WORK ZONE PAVEMENT MARKING REMOVAL	SHORT TERM PAVEMENT MARKING
4"		6"		24"	LETTERS & SYMBOLS	SQ FT		
YELLOW	WHITE	PARKING STALL WHITE	CROSS WALK WHITE	STOP BAR WHITE				
LF	LF	LF	LF	SQ FT	SQ FT	LF		
KEYES AVENUE								
STA. 200+22 TO 204+50	100		35	162	28		52	156
STA. 204+50 TO 209+50	130		28	76	26		61	182
STA. 209+50 TO 214+50	130	1,225				9.2	43	130
STA. 214+50 TO 219+50	130				28		62	186
STA. 219+50 TO 222+82	80						27	80
INDUSTRIAL DRIVE								
STA. 309+00 TO 310+00					27		18	54
MILL AVENUE								
STA. 116+00 TO 118+00					13		9	26
TOTALS	570	1,225	62	238	122	9.2	271	814
	1,795		300					

DEPRESSED CURB AND GUTTER SCHEDULE			
BEGINNING STATION	ENDING STATION	LT./RT.	LENGTH (FT)
KEYES AVENUE			
200+26	200+34	RT.	20
200+26	200+31	LT.	12
200+90	201+32	LT.	42
200+90	201+38	RT.	48
201+47	201+76	RT.	29
201+51	201+83	LT.	32
202+74	202+89	RT.	15
203+02	203+30	RT.	28
204+43	204+72	LT.	34
204+47	204+62	RT.	15
205+30	205+57	LT.	27
205+36	205+64	RT.	28
205+90	206+18	RT.	28
206+15	206+54	LT.	39
206+32	206+46	RT.	14
206+98	207+13	RT.	15
207+58	208+47	LT.	89
207+60	207+65	RT.	5
207+93	208+79	RT.	86
208+99	210+58	RT.	159
212+47	212+79	RT.	32
213+02	213+29	LT.	27
213+43	213+82	LT.	39
214+81	215+36	RT.	55
215+84	216+14	RT.	30
216+51	216+90	LT.	31
218+54	218+86	RT.	31

SIGN SCHEDULE											
LOCATION	R1-1-30		W1-1		W13-1		D9-14 (24"x36")		D3-1		ORNAMENTAL SIGN POST, EACH
	NUMBER REQUIRED	AREA, SF	NUMBER REQUIRED	AREA, SF	NUMBER REQUIRED	AREA, SF	NUMBER REQUIRED	AREA, SF	NUMBER REQUIRED	AREA, SF	
MILL AVENUE											
105+00									2	3.76	1
114+09									2	3.76	1
115+28									2	3.76	1
117+69	1	5.00									1
117+72									2	3.76	1
KEYES AVENUE											
200+36									2	3.76	1
200+37	1	5.00									1
206+89									2	3.76	1
206+94	1	5.00									1
218+67	1	5.00					1	6.00			1
219+30									2	3.76	1
INDUSTRIAL DRIVE											
303+75			1	8.00	1	5.00					1
307+65			1	8.00	1	5.00					1
309+16									2	3.76	1
309+22	1	5.00									1
TOTAL	5	25.00	2	16.00	2	10.00	1	6.00	16	30.08	15

Plotted: February 1, 2010 @ 2:07 PM By: Kris Pump - Tab: 16--SCHEDULES (22x34)

Path: \\S:\P\RD\H40587\DWG\H40587.DWG FINAL ENG H40587-CVR

COPYRIGHT © 2010 ENGINEERING ENTERPRISES, INC.

FILE NAME	USER NAME = #USER#	DESIGNED - JAM, SWM	REVISED - 12/02/09
FILE#		DRAWN - KKP	REVISED - 01/22/10
PLOT SCALE = #SCALE#		CHECKED - JAM	REVISED - 02/03/10
PLOT DATE = #DATE#		DATE - 10/16/09	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

PROJECT NO. HPP-1468(004)	JOB NO. C-91-175-06
SHEET NO. 13 OF 92 SHEETS	STA. N/A TO STA. N/A

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	06-00015-00-PV	KANE	97	16
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT			CONTRACT NO. 63406	