

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	NHF			TE	NHF				
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80/20 FED CITY	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	
				1000-2A	1000-1A	Y050	Y046	X071-2A	X028-2A	Y007	X981-2A	
				ROADWAY	IL 26	FRONTAGE ROAD	BIKE PATH	US RTE 20 OVER PECATONICA RIVER	FRONTAGE ROAD OVER "WESTERN" TRIB. TO PECATONICA SN:089-2018	FRONTAGE ROAD OVER "EASTERN" TRIB. TO PECATONICA SN:089-2025	US RTE 20 OVER JANE ADDAMS TRAIL	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1									
50500505	STUD SHEAR CONNECTORS	EACH	10,188						10,188			
50800105	REINFORCEMENT BARS	POUND	53,639	29		90				52,500	1,020	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	415,370					347,380				67,990
50800515	BAR SPLICERS	EACH	184					92				92
51100100	SLOPE WALL 4 INCH	SQ YD	65									65
51100500	BITUMINOUS COATED AGGREGATE SLOPEWALL, 6"	SQ YD	566									566
51201500	FURNISHING STEEL PILES HP10X57	FOOT	795									795
51201600	FURNISHING STEEL PILES HP12X53	FOOT	8,822					8,822				
51201700	FURNISHING STEEL PILES HP12X74	FOOT	815									815
51202305	DRIVING PILES	FOOT	10,432					8,822				1,610
51203500	TEST PILE STEEL HP10X57	EACH	2									2
51203600	TEST PILE STEEL HP12X53	EACH	8					8				
51203700	TEST PILE STEEL HP12X74	EACH	2									2
51204650	PILE SHOES	EACH	176					156				20
51500100	NAME PLATES	EACH	3					1	1			1
52000208	FINGER PLATE EXPANSION JOINT, 3"	FOOT	45.1					45.1				
52000212	FINGER PLATE EXPANSION JOINT, 4"	FOOT	45.1					45.1				
52000600	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	90.2					90.2				
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12					12				
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	18					18				
52100030	ELASTOMERIC BEARING ASSEMBLY, TYPE III	EACH	12					12				
52100520	ANCHOR BOLTS, 1"	EACH	24					24				
52100530	ANCHOR BOLTS, 1 1/4"	EACH	12					12				
52100540	ANCHOR BOLTS, 1 1/2"	EACH	68					60				8
54002020	EXPANSION BOLTS 3/4 INCH	EACH	38								38	
54003000	CONCRETE BOX CULVERTS	CU YD	257							257.0		
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	342	342								
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	90	90								
542A1921	PIPE CULVERTS, CLASS A, TYPE 3 36"	FOOT	63	63								
542C0229	PIPE CULVERTS, CLASS C, TYPE 1 24"	FOOT	58	58								
542C1975	PIPE CULVERTS, CLASS C, TYPE 3 90"	FOOT	67								67	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	70	70								
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	188	100		88						
542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	173	173								

F.A.P. RTE. 301	SECTION 177-2 (-1A, B-1, VB-1)	COUNTY STEPHENSON	TOTAL SHEETS 386	SHEET NO. 10
STA. TO STA.		ILLINOIS FED. AID PROJECT		
P-92-029-02 CONTRACT #64799		S00-03 OF 07		

△ NON-PARTICIPATING ITEM (00% STATE)
 * SPECIALITY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.P. ROUTE 301 (US RTE. 20)
 FROM BOLTON ROAD TO WEST OF IL RTE. 26
 SUMMARY OF QUANTITIES



SCALE: NONE
 DATE: 01-22-10
 DRAWN BY SJV
 CHECKED BY RMH