

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	177-2 (-1A, B-1, VB-1)	STEPHENSON	386	24
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
P-92-029-02		SCHED-01 OF 15		
CONTRACT #64799				

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)				
STATION OFFSET - STATION OFFSET				UNIT
US20				
550+46		75	LT	12
550+50		75	LT	12
TOTAL FOR 1000-2A ROADWAY:				24
FRONTAGE ROAD				
98+72		13	LT	12
98+72		13	LT	12
129+57		30	RT	6
129+66		26	RT	14
129+76		11	RT	8
129+84		23	RT	12
130+05		18	LT	8
130+35		20	LT	10
130+36		38	RT	8
131+02		7	RT	6
139+17		41	LT	8
139+45		44	LT	12
158+43		6	LT	8
158+43		6	LT	8
158+52		7	LT	12
159+00		2	LT	8
159+00		18	RT	15
159+10		45	RT	15
166+31		12	LT	6
166+42		58	LT	10
167+04		40	LT	8
169+65		12	LT	6
FRONTAGE ENTRANCE				
100+00		82	LT	8
100+75		123	LT	12
HEINE ROAD				
18+64		26	LT	6
TOTAL FOR Y050 FRONTAGE ROAD:				238
TOTAL QUANTITY:				262

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)				
STATION OFFSET - STATION OFFSET				UNIT
FRONTAGE ROAD				
98+03		9	RT	20
99+72		48	RT	20
129+28		47	RT	20
129+33		33	RT	24
129+64		22	RT	16
129+87		8	RT	18
130+07		17	RT	16
139+25		45	LT	18
TOTAL FOR Y050 FRONTAGE ROAD:				152
TOTAL QUANTITY:				152

20101000 TEMPORARY FENCE				
STATION OFFSET - STATION OFFSET				UNIT
KLEVER RD				
5578+80		5582+65		465
TOTAL FOR Y046 BIKE PATH:				465
TOTAL QUANTITY:				465

20101100 TREE TRUNK PROTECTION				
STATION OFFSET - STATION OFFSET				UNIT
US20				
570+68		135	LT	12
570+68		135	LT	8
TOTAL FOR 1000-2A ROADWAY:				20
FRONTAGE ROAD				
112+88		82	LT	10
112+99		87	LT	8
113+09		85	LT	12
132+91		51	RT	10
132+92		51	RT	10
TOTAL FOR Y050 FRONTAGE ROAD:				50
TOTAL QUANTITY:				70

20200300 EARTH EXCAVATION FOR EROSION CONTROL				
STATION OFFSET - STATION OFFSET				UNIT
US20				
467+40		32	LT - SEDIMENT BASIN	80
504+14		91	LT - SEDIMENT BASIN	80
516+00		101	LT - SEDIMENT BASIN	80
530+72		111	LT - SEDIMENT BASIN	80
570+25		153	LT - SEDIMENT BASIN	80
583+90		163	LT - SEDIMENT BASIN	80
596+25		115	LT - SEDIMENT BASIN	80
TOTAL FOR 1000-2A ROADWAY:				560
FRONTAGE ROAD				
103+44		61	LT - SEDIMENT BASIN	80
104+18		60	LT - SEDIMENT BASIN	80
128+76		52	RT - SEDIMENT BASIN	80
129+66		50	RT - SEDIMENT BASIN	80
155+40		69	RT - SEDIMENT BASIN	80
156+54		70	RT - SEDIMENT BASIN	80
TOTAL FOR Y050 FRONTAGE ROAD:				480
TOTAL QUANTITY:				1,040

20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL				
STATION OFFSET - STATION OFFSET				UNIT
US20				
477+00		536+64		3,760
544+49		569+10		23,680
570+64		631+00		3,270
US20 Excess Topsoil Removal				
477+00		536+64		11,650
544+49		569+10		2,730
570+64		631+00		4,085
TOTAL FOR 1000-2A ROADWAY:				49,175
FRONTAGE ROAD Excess Topsoil Removal				
95+92.35		133+00.00		450
133+00.00		182+00.00		-80
7+00.00		7+35.00		-75
HEINE ROAD Excess Topsoil Removal				
8+00.00	TO	22+38.96		160
7+00.00	TO	9+00.00		-120
TOTAL FOR Y050 FRONTAGE ROAD:				335
TOTAL QUANTITY:				49,510

20800150 TRENCH BACKFILL			
STATION PIPE LENGTH			CU YD
FRONTAGE ROAD			
173+35	98	1.579	155
175+85	86	0.723	62
178+25	102	0.175	18
179+60	135	0.116	16
TOTAL FOR Y050 FRONTAGE ROAD:			250
TOTAL QUANTITY:			250

21101505 TOPSOIL EXCAVATION AND PLACEMENT			
STATION		STATION	UNIT
US20			
477+00.00		536+63.92	11,830
544+49.21		569+10.40	3,765
570+64.37		631+00.00	9,730
TOTAL FOR 1000-2A ROADWAY:			25,325
FRONTAGE ROAD			
95+92.35		133+00.00	5,425
133+00.00		182+00.00	8,755
7+00.00		7+35.00	75
TOTAL FOR Y050 FRONTAGE ROAD:			16,330
TOTAL QUANTITY:			41,655

25000100 SEEDING, CLASS 1					
STATION OFFSET - STATION OFFSET				ACRE	
FRONTAGE ROAD					
171+00	RT	-	173+30	RT	0.07
174+00	RT	-	176+76	RT	0.05
177+18	RT	-	182+00	RT	0.16
173+00	LT	-	181+20	LT	0.75
181+56	LT	-	182+61	LT	0.13
TOTAL FOR Y050 FRONTAGE ROAD:				1.25	
TOTAL QUANTITY:				1.25	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 301 (US RTE. 20)
FROM BOLTON ROAD TO WEST OF IL RTE. 26
SCHEDULE OF QUANTITIES

SCALE:
DATE: 01-22-10

DRAWN BY: AJP
CHECKED BY: RMH

