F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	177-2 (-1A, B-1, VB-1)	STEPHENSON	386	36
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

P-92-029-02
CONTRACT #64799

SCHED-13 OF 15

78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6" FOOT

	STATION	OFFSET	-	STATION	OFFSET		UNIT
IL26							
	11.00	RT 724+06	-	726+47	WHT	SK DSH	60
	11.00	RT 726+47	-	728+86	WHT	LANE	239
	45.00	RT 728+53	-	728+63	WHT	X WALK	162
	7.00	LT 730+06	-	732+78	WHT	MEDIAN	550
	11.00	LT 732+80		734+87	WHT	SK DSH	52
TOTAL FOR 1000-1A IL 26							1064
TOTAL QUANTITY:							1064

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12" FOOT

	STATION	OFFSET	-	STATION	OFFSET		UNIT
US20							
	728+53	RT 45.00	-	728+63	WHT	X WALK	270
	730+06	LT 7.00	-	732+80	WHT	MEDIAN	49
	730+03	RT 4.00	-	734+87	YEL	MEDIAN	220
	730+00	LT 10.00	-	732+78	YEL	DIAG	50
	730+00	RT 8.00	-	734+85	YEL	DIAG	221
	728+50	RT 45.00	-	728+62	WHT	X WALK	265
TOTAL FOR 1000-2A ROADWAY:							1075
TOTAL QUANTITY:							1075

78001110 PAINT PAVEMENT MARKING - LINE 4" FOOT

	STATION	OFFSET	-	STATION	OFFSET		UNIT
FRONTAGE ROAD							
		CL 94+00	-	101+75	YEL	SK DSH	190
		CL 95+50	-	101+75	YEL	CL	625
		CL 102+25		109+00	YEL	CL	675
	11.00	LT 95+50	-	101+75	WHT	EDGE	625
	11.00	LT 102+25	-	129+50	WHT	EDGE	2,735
	11.00	RT 95+50	-	129+50	WHT	EDGE	3,377
		CL 102+25	-	113+00	YEL	CL	1,075
		CL 109+00	-	113+00	YEL	SK DSH	100
		113+00	-	129+50	YEL	SK DSH	410
		CL 129+50	-	135+00	YEL	SK DSH	130
		CL 129+50	-	138+00	YEL	CL	850
		CL 135+00	-	143+50	YEL	CL	850
		CL 138+00	-	143+50	YEL	SK DSH	130
	11.00	LT 129+50	-	143+50	WHT	EDGE	1,400
	11.00	RT 129+50	-	143+50	WHT	EDGE	1,400
		CL 143+50	-	165+50	YEL	CL	550
	11.00	LT 143+50	-	165+50	WHT	EDGE	2,198
	11.00	RT 143+50	-	165+50	WHT	EDGE	2,202
		CL 165+50	-	172+00	YEL	SK DSH	160
		CL 165+50	-	173+00	YEL	CL	750
		CL 172+00	-	178+50	YEL	CL	650
		CL 173+00	-	178+50	YEL	SK DSH	130
	11.00	LT 165+50	-	170+40	WHT	EDGE	488
	11.00	RT 165+50	-	170+40	WHT	EDGE	491
		CL 178+50	-	180+80	YEL	CL	50
FRONTAGE ENT.							
	18.00	LT 6+30		7+68	WHT	EDGE	241
	15.00	RT 6+30		7+68	WHT	EDGE	277
HEINE ROAD							
		CL 8+00	-	22+36	YEL	CL	360
	11.00	LT 8+00	-	22+36	WHT	EDGE	1,448
	11.00	RT 8+00	-	22+36	WHT	EDGE	1,426
TOTAL FOR Y050 FRONTAGE ROAD:							25994
TOTAL QUANTITY:							25994

78001180 PAINT PAVEMENT MARKING - LINE 24" FOOT

	STATION	OFFSET	-	STATION	OFFSET	UNIT
IL 26	729+26	60.00LT	-	729+45	60.00RT	19
TOTAL FOR 1000-1A IL 26						19
FRONTAGE ROAD						
	180+50	0.00RT	-	180+50	15.00RT	15
	182+03	0.00RT	-	182+03	15.00RT	15
	7+40	0.00RT	-	7+40	20.00RT	20
HEINE ROAD						
	22+36	0.00RT	-	22+36	11.00RT	11
TOTAL FOR Y050 FRONTAGE ROAD:						61
TOTAL QUANTITY:						80

78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH

	STATION	-	STATION	COLOR	UNIT
US 20	576+00.00		591+00.00	AMBER	38
TOTAL FOR 1000-2A ROADWAY:					38
IL 26	726+52.00		728+86.00	CRYSTAL	13
	730+08.00		732+78.00	CRYSTAL	14
	730+08.00		734+87.00	AMBER	24
	730+08.00		734+87.00	AMBER	12
TOTAL FOR 1000-1A IL 26					63
TOTAL QUANTITY:					101

78200410 GUARDRAIL MARKERS, TYPE A EACH

	STATION	OFFSET	-	STATION	OFFSET	UNIT
FRONTAGE ROAD						
	154+20.00	RT		156+93.00	RT	273
	103+21.50	RT		104+02.75	RT	81
TOTAL FOR Y050 FRONTAGE ROAD:						354
TOTAL QUANTITY:						354

78201000 TERMINAL MARKER - DIRECT APPLIED EACH

	STATION	OFFSET	-	STATION	OFFSET	UNIT
FRONTAGE ROAD						
	103+21.50	RT				1
	104+02.75	RT				1
	154+20.00	RT				1
	156+93.00	RT				1
TOTAL FOR Y050 FRONTAGE ROAD:						4
TOTAL QUANTITY:						4

78300100 PAVEMENT MARKING REMOVAL SQ FT

	STATION		WIDTH (FT)	-	STATION	WIDTH (FT)	UNIT
US20							
	576+00	RT	SOLID	-	582+50		578
	576+00	RT	SOLID	-	580+66		1,040
	583+60		DOUBLE		590+68		472
	585+23		DOUBLE		590+68		363
TOTAL FOR 1000-2A ROADWAY:							2,453
IL 26							
	723+00	RT	SK DSH	-	729+00		50
	724+00	LT	SK DSH	-	729+00		42
	730+00	LT	SK DSH	-	736+13		51
TOTAL FOR 1000-1A IL 26							143
TOTAL QUANTITY:							2,596

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH

	STATION	-	STATION	UNIT
US 20	576+00.00		591+00.00	150
TOTAL FOR 1000-2A ROADWAY:				150
TOTAL QUANTITY:				150

A2C022G3 TREE, CARYA ILLINOINENSIS, CONTAINER GROWN, 3-GALLON EACH

PLANTED IN THE WETLAND AREA	29
TOTAL	29

A2C040G3 TREE, PLATANUS OCCIDENTALIS (SYCAMORE), CONTAINER GROWN, 3-GALLON

	EACH
PLANTED IN THE WETLAND AREA	28
TOTAL	28

A2C050G3 TREE, QUERCUS ELLIPSOIDALIS (HILL'S OAK), CONTAINER GROWN, 3-GALLON

	EACH
PLANTED IN THE WETLAND AREA	29
TOTAL	29

A2C060G3 TREE, QUERCUS PALISTRIS (PIN OAK), CONTAINER GROWN, 3-GALLON

	EACH
PLANTED IN THE WETLAND AREA	29
TOTAL	29

X0300015 CONCRETE WINGWALL REMOVAL EACH

	STATION	OFFSET	-	STATION	OFFSET	UNIT
FRONTAGE ROAD						
	155+88.0	RT				1
TOTAL FOR Y050 FRONTAGE ROAD:						1
TOTAL QUANTITY:						1

PARSONS BRINCKERHOFF

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 301 (US RTE. 20)
FROM BOLTON ROAD TO WEST OF IL RTE. 26

SCHEDULE OF QUANTITIES

SCALE:
DATE: 01-22-10
DRAWN BY A.P
CHECKED BY RMH