

GUARDRAIL		
STRUCTURE	GUARDRAIL MARKERS	TERMINAL MARKERS DIRECT APPLIED
	EACH	EACH
038-0197	18	4
038-0023	14	4
038-0184	10	4
TOTALS	54	12

SEEDING SCHEDULE								
SIDEROAD OR DESCRIPTION	STATION	SIDE	SEEDING	FURN	EROSION	NIT	PHOS	POT
			CL 2	EXC	CONTROL	FERT	FERT	FERT
			ACRE	CU YD	BLANKET	NUT	NUT	NUT
					SQ YD	LB	LB	LB
CR 1760 N	892+30	RT	0.01	1.5	52	0.9	0.9	0.9
CR 7	913+96	RT	0.01	1.5	52	0.9	0.9	0.9
CR 1730 N	913+96	LT	0.01	1.5	52	0.9	0.9	0.9
PE WMBTO	935+08	LT	0.01	0.8	28	0.9	0.9	0.9
PE WMBTO	937+95	RT	0.01	0.8	28	0.9	0.9	0.9
1680 N ROAD	939+04	RT	0.01	1.5	52	0.9	0.9	0.9
1675 N ROAD	941+42	RT	0.01	1.5	52	0.9	0.9	0.9
PE WMBTO	941+90	LT	0.01	0.8	28	0.9	0.9	0.9
CR 2280 E	953+94	RT	0.01	1.5	52	0.9	0.9	0.9
CR 1600 N	988+87.5	RT	0.01	1.5	52	0.9	0.9	0.9
CR 1600 N	988+87.5	LT	0.01	1.5	52	0.9	0.9	0.9
CR 1550 N	1016+25	RT	0.01	1.5	52	0.9	0.9	0.9
CR 1550 N	1016+25	LT	0.01	1.5	52	0.9	0.9	0.9
MBTO	1020+90	LT	0.01	0.8	28	0.9	0.9	0.9
CR 1500 N	1042+79	RT	0.01	1.5	52	0.9	0.9	0.9
CR 1500 N	1042+79	LT	0.01	1.5	52	0.9	0.9	0.9
CR 1400 N	1095+96.5	RT	0.01	1.5	52	0.9	0.9	0.9
CR 1400 N	1095+96.5	LT	0.01	1.5	52	0.9	0.9	0.9
CR 1330 N	1135+51	LT	0.01	1.5	52	0.9	0.9	0.9
CR 1200 N	1203+55	RT	0.01	1.5	52	0.9	0.9	0.9
CR 1200 N	1203+55	LT	0.01	1.5	52	0.9	0.9	0.9
PE WMBTO	1227+21	LT	0.01	0.8	28	0.9	0.9	0.9
CR 1170 N	1257+07	RT	0.01	1.5	52	0.9	0.9	0.9
CR 1170 N	1257+07	LT	0.01	1.5	52	0.9	0.9	0.9
PE WMBTO	1267+37	LT	0.01	0.8	28	0.9	0.9	0.9
MBTO	1293+14	LT	0.01	1.5	52	0.9	0.9	0.9
PE W MBTO	1310+98	LT	0.01	0.8	28	0.9	0.9	0.9
CR 1120 N	1323+27	RT	0.01	1.5	52	0.9	0.9	0.9
CR 1120 N	1323+27	LT	0.01	1.5	52	0.9	0.9	0.9
CR 1100 N	1349+63	LT	0.01	1.5	52	0.9	0.9	0.9
PE W MBTO	1366+61	RT	0.01	0.8	28	0.9	0.9	0.9
MBTO	1370+45	RT	0.01	1.5	52	0.9	0.9	0.9
PE W MBTO	477+53	LT	0.01	0.8	28	0.9	0.9	0.9
PE W MBTO	478+35	LT	0.01	0.8	28	0.9	0.9	0.9
MBTO	478+58	RT	0.01	0.8	28	0.9	0.9	0.9
PE W MBTO	479+17	LT	0.01	0.8	28	0.9	0.9	0.9
TOTAL			0.36	45.6	1584	32.4	32.4	32.4

FILE NAME =	USER NAME = carpenterdj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pwork\PIWIDOT\CARPENTERDJD0175591	366643-shit-details.DGN	DRAWN -	REVISED -					332	(3, D-IRS-2, (14, 15, 2)RS	IROQUOIS	15	6
	PLOT SCALE = 50,0000' / IN.	CHECKED -	REVISED -		SCALE: _____ SHEET NO. ____ OF ____ SHEETS STA. _____ TO STA. _____			CONTRACT NO. 66643				
	PLOT DATE = Jan 25, 2010 - 07:15:18 AM	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							