

MAINLINE SCHEDULE									
LOCATION	HOT MIX ASPHALT SURF. REM. 1 1/2"	BITUMINOUS MATERIALS PRIMECOAT	AGGREGATE PRIMECOAT	MIXTURE FOR CRACKS JOINTS & FLANGEWAYS	LEVELING BINDER (MACHINE METHOD) 3/4 INCH	LEVELING BINDER (HAND METHOD)	TEMPORARY RAMP	HOT MIX ASPHALT SURF. CSE. 1 1/2 INCH	AGG. SHLD. TY. B
STATION	SQ YD	GAL	TON	TON	TON	TON	SQ YD	TON	TON
STA 274+52 TO 569+38	104839	13629	419	31.5	4403	52.4	35.6	8807	2049
STA 569+38 TO 569+98	BRIDGE	OMISSION	SN-053-0062						
STA 569+98 TO 788+85	77820	10117	311	23.3	3269	39	35.6	6537	1521
STA 788+85 TO 790+85	BRIDGE	OMISSION	SN-053-0064						
STA 790+85 TO 851+47	21554	2802	86	6.5	906	10.8	35.6	1811	421
STA 851+47 TO 852+97	BRIDGE	OMISSION	SN-053-0065						
STA 852+97 TO 963+82	39413	5124	158	11.8	1656	19.7	54.5	3311	770
STATION EQUATION	STA 963+82/ BK	STA 20+27.8/AH							
STA 20+27.8 TO 40+59.34	16224	2109	65	4.9	682	8.1	56	1363	140
TOTALS	259850	33781	1039	78	10916	130	218	21829	4901

SIDEROADS, ENTRANCES, AND MAILBOX TURNOUTS						
LOCATION	HOT MIX ASPHALT SURF. REM. VAR. DEPHT	TEMPORARY RAMP	INCIDENTAL HOT MIX ASPHALT SURFACING	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	FURNISHED EXCAVATION
STATION	SQ YD	SQ YD	TON	GALLON	TON	CU YD
STA 274+52 TO 569+38						
TOTAL SIDEROADS(15)	2253	190	253	180	5	75
TOTAL DRIVEWAYS(25)	969	0	109	78	2	25
TOTAL MBTO/DW(10)	491	0	55	39	1	10
TOTAL MBTO(2)	49	0	5	4	0	2
STA 569+38 TO 569+98	BRIDGE	OMISSION	SN-053-0062			
STA 569+98 TO 788+85						
TOTAL SIDEROADS(8)	1422	114	160	114	3	40
TOTAL DRIVEWAYS(8)	348	0	39	28	1	8
TOTAL MBTO/DW(5)	291	0	33	23	1	5
TOTAL MBTO(3)	101	0	11	8	0	3
STA 788+85 TO 790+85	BRIDGE	OMISSION	SN-053-0064			
STA 790+85 TO 851+47						
TOTAL SIDEROADS(2)	322	23	36	26	1	10
TOTAL DRIVEWAYS(4)	136	0	15	11	0	4
TOTAL MBTO/DW(6)	372	0	42	30	1	6
TOTAL MBTO(3)	115	0	13	9	0	3
STA 851+47 TO 852+97	BRIDGE	OMISSION	SN-053-0064			
STA 852+97 TO 963+82						
TOTAL SIDEROADS(5)	810	65	91	65	2	20
TOTAL DRIVEWAYS(0)	0	0	0	0	0	0
TOTAL MBTO/DW(2)	110	0	12	9	0	2
TOTAL MBTO(0)	0	0	0	0	0	0
STATION EQUATION	STA 963+82/BK	STA 20+27.8/AH				
STA 20+27.8 TO 40+59.34						
TOTAL SIDEROADS(1)	132	33	15	11	0	5
TOTAL DRIVEWAYS(1)	150	0	17	12	0	1
TOTAL MBTO/DW(1)	58	0	7	5	0	1
TOTAL MBTO(0)	0	0	0	0	0	0
TOTALS	8129	425	913	652	17	220