

PAVEMENT MARKING SCHEDULE

LOCATION	THERM PLASTIC PVMT MKG 4" LINE WHITE FT	THERM PLASTIC PVMT MKG 4" LINE YELLOW FT	THERM PLASTIC PVMT MKG 6" LINE YELLOW FT	THERM PLASTIC PVMT MKG 8" LINE WHITE FT	THERM PLASTIC PVMT MKG 12" LINE YELLOW FT	THERM PLASTIC PVMT-MKG LETTERS SYMBOLS SQ FT	PAINT PVMT MKG 4" LINE WHITE FT	PAINT PVMT MKG 6" LINE YELLOW FT	PVMT RAISED REFLECTIVE MARKER EACH	PVMT RAISED REFLECTIVE MARKER REM EACH	PRISMATIC CURB REFLECTORS EACH	SHORT TERM PVMT MKG FT	WORK ZONE PVMT MKG REM SQ FT	TEMP PVMT MKG 4" LINE FT	TEMP PVMT MKG 6" LINE FT	TEMP PVMT MKG 8" LINE FT	TEMP PVMT MKG 12" LINE FT	TEMP PVMT-MKG LETTERS SYMBOLS SQ FT
STA 274+52 TO 569+38							117,944	14,744	369	360		8,846	983	58,972	7,372			
STA 569+38 TO 569+98	BRIDGE		OMISSION	SN-053-0062														
STA 569+98 TO 788+85							87,548	10,944	274	270		6,566	730	43,774	5,472			
STA 788+85 TO 790+85	BRIDGE		OMISSION	SN-053-0064														
STA 790+85 TO 851+47							24,248	3,032	76	70		1,819	202	12,124	1,516			
STA 851+47 TO 852+97	BRIDGE		OMISSION	SN-053-0065														
STA 852+97 TO 958+32							42,140	5,268	139	135		3,161	351	23,608	2,634			
STA 958+32 TO 963+82	1,100		138									165	19	1,233	138			
STATION EQUATION	STA 963+82/BK		STA 20+27.8/AH															
STA 20+27.8 TO 40+59.34	4,063	5,497	0	430	338	141			118		91	2400	267	9,560	0	430	338	141
PROJECT TOTALS	5,163	5497	138	430	338	141	271,880	33,988	976	835	91	22,957	2,552	149,271	17,132	430	338	141