

SIDE ROAD & ENTRANCES								
LOCATION	STATION	RT/LT	INCIDENTAL	BIT	HMA	TEMP.	FURN.	AGG
			HMA SURF	MATLS PR CT	SURF REM. VAR. DP	RAMP	EX*	PR CT
			TON	GAL	SQ YD	SQ YD	CU YD	TON
PE (IL 116)	3+70	LT	8.4	5.3	66.7			
PE	11+00	LT	10.7	6.8	85.0			0.2
3200 N	1525+30	RT/LT	18.2	11.6	144.4	21.3	4.0	0.3
PE	1540+45	RT	3.9	2.5	31.1			0.1
PE	1547+44	LT	3.1	2.0	24.4			0.0
PE	1554+31	LT	4.3	2.8	34.4			0.1
PE	1555+45	LT	4.5	2.8	35.6			0.1
3100 N	1578+03	RT	18.1	11.5	143.3	10.7	2.0	0.3
3100 N	1582+50	LT	16.8	10.7	133.3	10.7	2.0	0.3
3000 N	1631+45	RT/LT	18.5	11.7	146.7	21.3	4.0	0.3
PE	1651+90	LT	3.5	2.2	27.8			0.1
MBT	1652+43	RT	4.9	3.1	38.9			0.1
2900 N	1684+75	RT/LT	26.2	16.6	208.0	21.3	4.0	0.4
PE/MBT	1704+65	RT	4.0	2.6	31.9			0.1
MBT	1706+10	RT	1.1	0.7	8.9			0.0
PE	1706+10	LT	2.4	1.5	18.9			0.0
PE	1707+30	LT	0.8	0.5	6.7			0.0
2800 N	1737+84	RT/LT	28.2	17.9	223.9	21.3	4.0	0.4
PE	1784+54	LT	2.9	1.8	22.8			0.0
PE/MBT	1786+37	LT	2.3	1.5	18.3			0.0
2700 N	1790+97	RT/LT	7.8	5.0	62.3	21.3	4.0	0.1
PE	1807+15	RT	4.1	2.6	32.8			0.1
MBT	1807+15	LT	5.9	3.7	46.7			0.1
PE/MBT	1817+30	LT	5.7	3.6	45.6			0.1
2600 N	1844+30	RT/LT	28.5	18.1	226.1	21.3	4.0	0.5
PE	1881+63	RT	2.9	1.9	23.3			0.0
MBT	1882+55	LT	2.1	1.3	16.7			0.0
PE	1882+55	RT	2.1	1.3	16.7			0.0
PE	1883+54	RT	2.8	1.8	22.2			0.0
1400 E	1894+06	RT	16.0	10.2	127.2	10.7	2.0	0.3
2500 N	1901+33	RT	27.0	17.1	213.9	10.7	2.0	0.4
CE	1909+30	LT	2.4	1.5	18.9			0.0
CE	1910+61	LT	2.8	1.8	22.2			0.0
			301.8	186.0	2325.6	170.6	32.0	4.7

*PLACE FURNISHED EX AROUND SIDERAOD RADII. THIS AREA TO BE SEEDED, FERTILIZED AND MULCHED- NOT PAID FOR SEPERATELY BUT INCLUDED IN THE COST OF FURNISHED EXCAVATION

PERMANENT SURVEY MARKERS, TYPE 1				
LOCATION	DESCRIPTION	EXISTING MONUMENT	PERM SURV MK, TY 1 EACH	NOTE
IL 116 4+59 3' LT	SW CORN SEC. 21 T28 R1E	BRASS DISK	1	2
1499+26	E 1/4 SEC. 29 T28 R9E	BRASS DISK	1	2
	SE CORN SEC 29 T28N R9E	SURVEY NAIL		1
	W 1/4 SEC. 4 T27N R9E	PK NAIL		1
	NW CORN SEC. 9 T27N R9E	PK NAIL		1
1684+66 2.5' RT	NW CORN SEC. 16 T27 R9E	BRASS DISK	1	2
1711+24 3' RT	W 1/4 SEC. 16 T27 R9E	PK NAIL	1	2
1737+86 8' RT	SW CORN SEC. 16 T27 R9E	BRASS DISK	1	2
	NW CORN SEC. 33 T27N R9E	PK NAIL	1	2
	W 1/4 SEC. 33 T27N R9E	PK NAIL		1
TOTAL			6	

SEE COMMITMENT FILE FOR TIE POINTS

NOTE 1: RESIDENT TO RE-ESTABLISH MONUMENT, PAY ITEM FOR PERMANENT SURVEY MARKER TY 1 NOT TO BE USED

NOTE 2: RESIDENT TO RE-ESTABLISH MONUMENT AND FURNISH TIE SKETCHES TO D3 PLATS AND PLANS

FILE NAME =	USER NAME = sellnr	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
at\pwork\PW1001\SELLNR\d0173864\d366	22-sht-details.dgn	DRAWN - ---	REVISED - ---		796	(105,106)RS-3	FORD	10	6			
PLOT SCALE = 50.1355' / IN.	CHECKED - ---	REVISOR - ---	REVISED - ---		SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____			CONTRACT NO. 66922				
PLOT DATE = Jan 29, 2010 - 01:42:04 PM	DATE - ---	REVISED - ---	REVISED - ---	ILLINOIS FED. AID PROJECT								