

SUMMARY OF QUANTITIES				
CODE NO.	ITEM	UNIT	100% STATE	CONSTRUCTION TYPE CODE
			TOTAL QUANTITY	ROADWAY I000
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	959	959
20400800	FURNISHED EXCAVATION	CU YD	92	92
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	19063	19063
40600300	AGGREGATE (PRIME COAT)	TON	306	306
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	39	39
40600525	LEVELING BINDER (HAND METHOD), N50	TON	65	65
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	6272	6272
40600990	TEMPORARY RAMP	SQ YD	169	169
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	12574	12574
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	295	295
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	129754	129754
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3752	3752
48203017	HOT-MIX ASPHALT SHOULDERS, 5"	SQ YD	15990	15990
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6' ^{FOOT} POSTS	FOOT	50	50
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	12	12
63200310	GUARDRAIL REMOVAL	FOOT	650	650
66700095	PERMANENT SURVEY MARKERS	EACH	3	3
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	21542	21542
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	125491	125491
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	12050	12050
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	500	500
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1740	1740
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	152	152
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1731	1731
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11984	11984
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	500	500
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1740	1740
* 78000850	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	152	152
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	113507	113507
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	12050	12050
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	691	691
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	12	12
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	691	691
X0322729	MATERIAL TRANSFER DEVICE	TON	12574	12574

* SPECIALTY ITEMS

FILE NAME =	USER NAME = braboypc	DESIGNED - ---	REVISED - ---
ct:\pw_work\VPWIDOT\BRABOYPC\d0122687\d366946-shr-plans.dgn		DRAWN - ---	REVISED - ---
	PLOT SCALE = 50.0000' / IN.	CHECKED - ---	REVISED - ---
	PLOT DATE = Dec 28, 2009 - 03:55:07 PM	DATE - ---	REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
587	(135, 135 EXT/RS-6	BUREAU	___	3
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT			CONTRACT NO. 66946	