

MAINLINE												
LOCATION	WIDTH	LENGTH	AREA	HMA SURF REM 1-1/2"	HMA LEVEL BIND (HM)	LEVEL BINDER (MM) N50	HMA SC MIX "C" N50	MIX CR JTS FLANGEWYS	BIT MATLS PR CT	AGG PR CT	TEMP RAMP	AGG SHLD TY B
STATION	FT	FT	SQ YD	SQ YD	TON	TON	TON	TON	GAL	TON	SQ YD	TON
254+74 TO 267+50	VARIES	1276	5233.0	5233.0	2.6	219.8	439.6	1.6	680.3	10.5	12.0	96.9
267+50 TO 307+31	+27	3981	11943.0	10616.0	5.3	501.6	1003.2	3.2	1552.6	23.9	12.0	302.3
BR OMISSION SN 006-0098 308+03 TO 490+89	+27	18286.0	54858.0	48762.7	24.4	2304.0	4608.1	14.6	7131.5	109.7		1388.4
BR OMISSION SN 006-0097 491+79 TO 588+47	+27	9668.0	29004.0	25781.3	12.9	1218.2	2436.3	7.7	3770.5	60.2	12.0	734.1
BR OMISSION SN 006-0096 588+65 TO 749+00	+27	16035.0	48105.0	42760.0	21.4	2020.4	4040.8	12.8	6253.7	99.8		1217.5
IL 40 INTERSECTION*												
NORTH LEG	VAR.	100.0	542.0	542.0	0.3	22.8	45.5	0.2	70.5	1.1	12.0	
SOUTH LEG	VAR.	100.0	542.0	542.0	0.3	22.8	45.5	0.2	70.5	1.1	12.0	
TOTALS			144994.0	129004.0	64.5	6272.4	12544.9	38.7	18849.2	295.7	48.0	3751.4

*NOTE: IL 92 STA. 261+42.3 = IL 40 STA. 794+73.8 QUANTITY PROVIDED FOR 100' NORTH AND SOUTH OF THIS LOCATION

BITUMINOUS SHOULDER					
LOCATION	SIDE	LENGTH	AREA	HMA SHLD 5"	EX & GRADING EXIST SHLD
STATION		FT	SQ. YD.	SQ YD	UNIT
267+50 TO 307+31	LT & RT	3981	1327	1327	79.6
BR OMISSION SN 006-0098 308+03 TO 490+89	LT & RT	18286.0	6095	6095	365.7
BR OMISSION SN 006-0097 491+79 TO 588+47	LT & RT	9668.0	3223	3223	193.4
BR OMISSION SN 006-0096 588+65 TO 749+00	LT & RT	16035.0	5345	5345	320.7
TOTALS				15990.0	959.4

PERMANENT SURVEY MARKERS	
LOCATION	PERMANENT SURVEY MARKERS EACH
SW CORNER SECTION 4	1
NW CORNER SECTION 10	1
N QUARTER CORNER, SECTION 10	1
TOTAL	3

ALL SECTION CORNERS TO BE ESTABLISHED BY LICENSSED LAND SURVEYOR AND REGISTERED AT THE COUNTY COURT HOUSE-INCLUDED IN THE COST OF PERMANENT SURVEY MARKERS
SEE COMMITMENT FILE FOR TIE POINTS

SIDE ROAD & ENTRANCES									
LOCATION	TYPE	RT/LT	HMA SURF CSE MIX C, N50	INCIDENTAL HMA SURF	BIT MATLS PR CT	HMA SURF REM. 1-1/2"	TEMP. RAMP	FURN. EX*	AGG PR CT
			TON	TON	GAL	SQ YD	SQ YD	CU YD	TON
0.00 HENRY COUNTY LINE									
0.1	PE	LT		2.0	2.0				0.1
0.12	MAILBOX TURNOUT	RT		1.0	1.0				0.1
0.4	PE	LT		2.0	2.0	15.0			0.1
0.4	MAILBOX TURNOUT	RT		1.0	1.0				0.1
0.5	PE	RT		2.0	2.0				0.1
0.52	SIDEROAD E35TH RD	LT&RT		25.0		200.0	15.0	4.0	0.6
0.55	CE	LT		6.0	4.0	45.0			0.2
0.57	PE	LT		2.0	2.0	15.0			0.1
0.6	CE	RT		4.0	4.0				0.2
0.61	CE	LT		4.0	4.0	25.0			0.2
0.62	CE	LT		4.0	4.0	25.0			0.2
0.63	CE	RT		4.0	4.0				0.2
0.9	PE	RT		2.0	2.0	15.0			0.1
1.5	PE	LT		2.0	2.0				0.1
1.5	MAILBOX TURNOUT	RT		1.0	1.0				0.1
1.51	PE	RT		2.0	2.0				0.1
1.8	PE	RT		2.0	2.0				0.1
2	SIDEROAD 200 E RD	RT<		25.0	15.0		15.0	4.0	0.6
2.2	PE	LT		2.0	2.0				0.1
2.4	PE	LT		2.0	2.0				0.1
2.6	CE	LT		4.0	4.0				0.2
2.7	PE & MAILBOX TURNOUT	LT		3.0	3.0				0.1
3	SIDEROAD 300 E RD	LT&RT		25.0	15.0		15.0	4.0	0.6
3.5	PE	LT		2.0	2.0				0.1
3.5	MAILBOX TURNOUT	RT		1.0	1.0				0.1
3.7	PE	RT		2.0	2.0				0.1
3.75	IL 172	RT	30		10.0				0.3
4	SIDEROAD 400 E RD	RT		13.0	8.0	70.0	8.0	2.0	0.3
4.05	PE	RT		2.0	2.0				0.1
4.25	SIDEROAD 425 E RD	LT&RT		25.0	15.0	170.0	15.0	4.0	0.6
5	SIDEROAD 500 EAST RD	LT		13.0	8.0		15.0	2.0	0.3
5.1	PE	RT		2.0	2.0				0.1
5.4	PE	LT		2.0	2.0				0.1
5.6	PE	LT		2.0	2.0				0.1
5.7	CE	RT		3.0	4.0				0.2
5.9	PE	LT		2.0	2.0	20.0			0.1
6	PE	RT		2.0	2.0				0.1
6.1	SIDEROAD 600 E RD	LT&RT		25.0	15.0		15.0	4.0	0.6
6.82	PE	LT		2.0	15.0				0.1
7	SIDEROAD 700 E RD	LT&RT		25.0	15.0		15.0	4.0	0.6
7.3	PE	RT		2.0	2.0				0.1
8	CE	RT		4.0	4.0				0.2
8.4	CE	RT		4.0	4.0				0.2
8.4	MAILBOX TURNOUT	LT		1.0	1.0				0.1
8.5	SIDEROAD 850 E RD	LT & RT		25.0	15.0	150.0	8.0	4.0	0.6
8.9 END PROJECT									
TOTALS			30.9	294.6	213.0	750.0	121.0	32.0	9.8

*PLACE FURNISHED EX AROUND SIDEROAD RADII. THIS AREA TO BE SEEDED, FERTILIZED AND MULCHED- NOT PAID FOR SEPERATELY BUT INCLUDED IN THE COST OF FURNISHED EXCAVATION

FILE NAME =	USER NAME = braboypc	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw-work\VPWIDOT\BRABOYPC\0122687\436946-sht-plans.dgn	DRAWN - ---	REVISED - ---	587			(135, 135 EXTRS-6)	BUREAU	8	5	
PLOT SCALE = 50.0000' / IN.	CHECKED - ---	REVISED - ---	CONTRACT NO. 66946							
PLOT DATE = Dec 28, 2009 - 03:55:16 PM	DATE - ---	REVISED - ---	FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT							
				SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____				