

SUMMARY OF QUANTITIES			URBAN 100% STATE	
CODE NO.	ITEM	UNIT	CONSTRUCTION CODE TYPE:	
			TOTAL QUANTITY	1000-2A ROADWAY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4572	4572
40600300	AGGREGATE (PRIME COAT)	TON	64	64
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	10	10
40600535	LEVELING BINDER (HAND METHOD), N70	TON	16	16
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1778	1778
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600990	TEMPORARY RAMP	SQ YD	77	77
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2684	2684
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	37198	37198
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	120	120
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	32	32
44213100	PAVEMENT FABRIC	SQ YD	32	32
44213200	SAW CUTS	FOOT	504	504
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	285	285
48203100	HOT-MIX ASPHALT SHOULDERS	TON	740	740
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4160	4160
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	230.4	230.4
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9170	9170
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4200	4200
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	6196	6196
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	32	32
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	458	458
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	115.2	115.2
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	23017	23017
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2100	2100
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	3098	3098
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	16	16
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	152	152
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	123	123
Z0017100	DOWEL BARS	EACH	200	200
X0322729	MATERIAL TRANSFER DEVICE	TON	2684	2684

* SPECIALTY ITEMS

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -
ct:\pw_work\PWIDOT\DUNCANBD\0123210\0365949-sheets.DGN		DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = Jan 19, 2010 - 05:01:08 PM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 46	SECTION (2,2-1)RS-3	COUNTY LASALLE	TOTAL SHEETS 17	SHEET NO. 3
CONTRACT NO. 66949				
ILLINOIS FED. AID PROJECT				

REV.