

STRIPING SCHEDULE

X7800620 X7800620 X7800630 78004200 78004220 78004230 78004280 78004250 78004250 78004280

STATION TO STATION	SIDE	DESCRIPTION	URETHANE PAVEMENT MARKING			PREFORMED PLASTIC, TYPE B - INLAID							
			5"	5"	6"	LETTERS	5"	6"	8"	12"	12"	24"	
			WHITE	YELLOW	WHITE	SYMBOLS	WHITE	WHITE	WHITE	WHITE	YELLOW	WHITE	
			FOOT			SQ FT	FOOT						
IL 57													
30+15.00	59+35.00	LT	EDGE LINE	2920.0									
30+15.00	35+09.21	CL	NO PASSING		988.4								
35+09.21	43+23.50	LT	EDGE LINE		814.3								
35+09.21	43+23.50	RT	EDGE LINE		814.3								
43+99.60	45+99.60	LT	TURN LANE			200.0							
45+99.60	48+97.68	LT	SKIP-DASH		76.0								
43+99.60	45+99.60	LT	TURN ARROWS (3)			46.8							
43+99.60	56+59.00	LT	EDGE LINE		1259.4								
43+99.60	56+59.00	RT	EDGE LINE		1259.4								
57+37.72	59+35.00	LT	TURN LANE			197.3							
57+37.72	59+35.00	LT	TURN ARROWS (2)			31.2							
57+38.72	59+35.00	LT	EDGE LINE		196.3								
57+38.72	59+35.00	RT	EDGE LINE		196.3								
30+15.00	42+01.85	RT	EDGE LINE	1186.9									
37+21.85	39+61.85	RT	SKIP-DASH			60.0							
39+61.85	42+48.80	RT	TURN LANE					287.0					
39+61.85	42+48.80	RT	TURN ARROWS (3)			46.8							
43+47.64	43+56.68	RT	EDGE LINE	9.0									
43+41.76	43+62.40	RT	CHANNELIZATION							21.0			
45+39.37	55+36.39	RT	EDGE LINE	997.0									
56+86.02	56+92.44	RT	EDGE LINE	6.4									
56+80.02	56+98.32	RT	CHANNELIZATION							20.0			
58+81.04	59+35.00	RT	EDGE LINE	54.0									
IL 96													
32+00.00	36+66.64	LT	EDGE LINE	466.6									
37+33.49	42+42.41	LT	EDGE LINE	508.9									
44+02.18	55+80.93	LT	EDGE LINE	1178.8									
32+00.00	36+76.00	LT	EDGE LINE		476.0								
32+00.00	36+76.00	RT	EDGE LINE		476.0								
37+25.00	43+91.00	LT	EDGE LINE		666.0								
37+25.00	43+91.00	RT	EDGE LINE		666.0								
44+78.39	46+33.95	LT	TURN LANE			155.6							
44+78.39	46+33.95	LT	TURN ARROWS (2)			31.2							
46+33.95	48+63.48	LT	SKIP-DASH			58.0							
44+71.00	55+29.00	LT	EDGE LINE		1058.0								
44+71.00	55+29.00	RT	EDGE LINE		1058.0								
51+31.52	53+61.05	RT	SKIP-DASH			58.0							
53+61.05	55+21.66	RT	TURN ARROWS (2)			31.2							
53+61.05	55+21.66	RT	TURN LANE			160.6							
56+09.00	57+24.32	LT	EDGE LINE		115.3								
56+09.00	57+57.60	RT	EDGE LINE		148.6								
32+00.00	36+28.47	RT	EDGE LINE	428.5									
37+44.48	42+75.67	RT	EDGE LINE	531.2									
44+19.12	55+97.83	RT	EDGE LINE	1178.7									
SUB-TOTALS				9466.0	10192.3	965.4	187.2	0.0	0.0	287.0	0.0	41.0	0.0
TOTALS				120488.7	120676.1	965.4	381.6	24230.0	208.0	7395.4	1404.0	41.0	144.0
USE				241165		966	382	24230	208	7396	1445	144	

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
e:\pwwork\p\WIDOT\LAUGHLINRL\0182983\009-D672A09-ahs-schedule0.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: none SHEET NO. 11 OF 18 SHEETS STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
172	1-(1,2,3,4,5)RS	ADAMS	165	19
CONTRACT NO. 72A09				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				