

PAVEMENT PATCHING CLASS B SCHEDULE

PATCH NUMBER	STATION	LENGTH	WIDTH	44200934	44200942	44200944	44201294	44201296	Z0017202	44213200	44213100
				TYPE II 8 INCH	TYPE III 8 INCH	TYPE IV 8 INCH	CLASS B PATCH EXPANSION JOINT	DEFORMED BARS EXPANSION JOINT	DOWEL BARS 1 1/2"	SAW CUTS	PAVEMENT FABRIC
				SQ YD			FOOT	EACH		FOOT	SQ YD
FAI 172 NORTHBOUND											
	122+62	12.0	12		16.0		16.0	14	14	60.0	16.0
	122+62	12.0	12		16.0		16.0	14	14	60.0	16.0
FAI 172 SOUTHBOUND											
	147+52	12.0	12		16.0		16.0	14	14	60.0	16.0
	147+52	12.0	12		16.0		16.0	14	14	60.0	16.0
	177+72	12.0	12		16.0		16.0	14	14	60.0	16.0
	177+72	12.0	12		16.0		16.0	14	14	60.0	16.0
IL 57 INTERCHANGE											
RAMP A											
	4+00	12.0	16		21.3		16.0	14	14	68.0	21.3
B1	4+13	6.0	16	10.7					28	50.0	
B2	5+20	6.0	16	10.7					28	50.0	
B3	6+80	6.0	16	10.7					28	50.0	
B4	13+98	6.0	16	10.7					28	50.0	
B5	14+48	6.0	16	10.7					28	50.0	
B6	23+35	6.0	16	10.7					28	50.0	
B7	27+23	18.0	16			32.0			28	86.0	32.0
RAMP B											
B8	1+67	6.0	16	10.7					28	50.0	
B9	2+15	6.0	16	10.7					28	50.0	
B10	3+18	6.0	16	10.7					28	50.0	
B11	5+75	6.0	16	10.7					28	50.0	
B12	6+80	6.0	16	10.7					28	50.0	
B13	8+20	6.0	16	10.7					28	50.0	
B14	8+80	6.0	16	10.7					28	50.0	
B15	10+36	6.0	16	10.7					28	50.0	
B16	10+75	6.0	16	10.7					28	50.0	
B17	12+78	6.0	16	10.7					28	50.0	
B18	13+13	6.0	16	10.7					28	50.0	
B19	13+77	6.0	16	10.7					28	50.0	
B20	14+30	6.0	16	10.7					28	50.0	
B21	14+77	6.0	16	10.7					28	50.0	
B22	17+50	6.0	16	10.7					28	50.0	
	18+00	12.0	16		21.3		16.0	14	14	68.0	21.3
RAMP C											
	3+64	12.0	16		21.3		16.0	14	14	68.0	21.3
B23	4+47	6.0	16	10.7					28	50.0	
B24	7+16	6.0	16	10.7					28	50.0	
B25	8+37	6.0	16	10.7					28	50.0	
B26	11+50	6.0	16	10.7					28	50.0	
B27	25+50	6.0	16	10.7					28	50.0	
RAMP D											
B28	1+36	6.0	16	10.7					28	50.0	
B29	2+30	6.0	16	10.7					28	50.0	
B30	5+70	6.0	16	10.7					28	50.0	
B31	6+20	6.0	16	10.7					28	50.0	
B32	6+80	6.0	16	10.7					28	50.0	
B33	7+15	6.0	16	10.7					28	50.0	
B34	10+51	6.0	16	10.7					28	50.0	
B35	11+21	6.0	16	10.7					28	50.0	
B36	12+30	6.0	16	10.7					28	50.0	
B37	15+30	11.0	16			19.6			28	65.0	19.6
B38	16+69	6.0	16	10.7					28	50.0	
B39	17+03	8.8	16			15.6			28	58.4	15.6
B40	18+00	6.0	16	10.7					28	50.0	
B41	20+45	11.0	16			19.6			28	65.0	19.6
B42	21+32	6.0	16	10.7					28	50.0	
B43	23+10	14.0	16			24.9	16.0	14	14	74.0	24.9
SUB-TOTALS				406.6	239.6	32.0	160.0	140	1316	2812.4	271.6

FILE NAME =
 USER NAME = laughlinr1
 DRAWN -
 CHECKED -
 DATE -
 PLOT SCALE = 100.0002' / IN.
 PLOT DATE = Feb-01-2010 09:34:22AM

DESIGNED -
 REVISIONS -
 REVISIONS -
 REVISIONS -
 REVISIONS -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
 SCALE: none SHEET NO. 16 OF 18 SHEETS STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
172	1-(1,2,3,4,5)RS	ADAMS	165	24
CONTRACT NO. 72A09				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				