

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES				HMA ROADWAY 100% STATE	SN 059-0042 100% STATE	SN 059-0044 100% STATE	SN 059-0045 100% STATE
				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	SFTY-2A	SFTY-2A	SFTY-2A
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1			
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1			
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15			
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1			1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	16			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	15,479	15,479			
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	54,860	10,060		6,400	38,400
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,107	1,107			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2,650	2,650			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	941	941			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	149	149			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,460	2,460			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	462.5			462.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	462.5			462.5	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	15	15			
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	6	6			
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	30	30			
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	3,200			3,200	
* 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	125	125			
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	10,060	10,060			
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	1,107	1,107			

*Specialty Items

FILE NAME :	USER NAME : loughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
et\pvc\work\PWIDOT\LAUGHLINRL\dms25312\672860-S00.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	55	59RS-2, BR	MACOUPIN	100	8
		CHECKED -	REVISED -						CONTRACT NO. 72A60						
		DATE -	REVISED -						ILLINOIS FED. AID PROJECT						