

| SUMMARY OF QUANTITIES | | | 100% STATE | CONSTRUCTION TYPE CODE | | |
|-----------------------|---|--------|------------------|------------------------|------------|--|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | RURAL 1000 | URBAN 1000 | |
| 40200800 | AGGREGATE SURFACE COURSE, TYPE B | TON | 58 | 51 | 7 | |
| 40600100 | BITUMINOUS MATERIALS (PRIME COAT) | GALLON | 11043 | 9341 | 1702 | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 221 | 187 | 34 | |
| 40600635 | LEVELING BINDER (MACHINE METHOD), N70 | TON | 4638 | 3923 | 715 | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 1 | 1 | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 630 | 630 | | |
| 40600990 | TEMPORARY RAMP | SQ YD | 407 | 288 | 119 | |
| 40603315 | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70 | TON | 9276 | 7847 | 1429 | |
| 40800050 | INCIDENTAL HOT-MIX ASPHALT SURFACING | TON | 251 | 152 | 99 | |
| 44000151 | HOT-MIX ASPHALT SURFACE REMOVAL, 1/2" | SQ YD | 96962 | 88260 | 8702 | |
| 44000158 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" | SQ YD | 12840 | 4527 | 8313 | |
| 44004250 | PAVED SHOULDER REMOVAL | SQ YD | 2427 | 2427 | | |
| 44201777 | CLASS D PATCHES, TYPE II, 11 INCH | SQ YD | 278 | | 278 | |
| 44201781 | CLASS D PATCHES, TYPE III, 11 INCH | SQ YD | 32 | | 32 | |
| 44201783 | CLASS D PATCHES, TYPE IV, 11 INCH | SQ YD | 64 | | 64 | |
| 44201798 | CLASS D PATCHES, TYPE I, 13 INCH | SQ YD | 941 | 828 | 113 | |
| 44201803 | CLASS D PATCHES, TYPE II, 13 INCH | SQ YD | 1273 | 1175 | 98 | |
| 44201807 | CLASS D PATCHES, TYPE III, 13 INCH | SQ YD | 393 | 393 | | |
| 44201809 | CLASS D PATCHES, TYPE IV, 13 INCH | SQ YD | 700 | 700 | | |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 1570 | 1447 | 123 | |
| 48203029 | HOT-MIX ASPHALT SHOULDERS, 8" | SQ YD | 2427 | 2427 | | |
| *63000001 | STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS | FOOT | 425 | 425 | | |
| *63000025 | STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES | FOOT | 25 | 25 | | |
| *63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT | EACH | 4 | 4 | | |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 200 | 200 | | |
| 66700205 | PERMANENT SURVEY MARKERS, TYPE I | EACH | 2 | | 2 | |
| 67000500 | ENGINEER'S FIELD OFFICE, TYPE B | CAL MO | 6 | 3 | 3 | |
| 67100100 | MOBILIZATION | L SUM | 1 | 0.5 | 0.5 | |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | 0.5 | 0.5 | |
| 70100500 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 | L SUM | 1 | 1 | | |
| 70100600 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701336 | L SUM | 1 | 0.5 | 0.5 | |

| SUMMARY OF QUANTITIES | | | 100% STATE | CONSTRUCTION TYPE CODE | | |
|-----------------------|--|-------|------------------|------------------------|------------|--|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | RURAL 1000 | URBAN 1000 | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 17545 | 15022 | 2523 | |
| 70300210 | TEMPORARY PAVEMENT MARKING, LETTERS AND SYMBOLS | SQ FT | 166 | | 166 | |
| 70300220 | TEMPORARY PAVEMENT MARKING LINE 4" | FOOT | 116456 | 104021 | 12435 | |
| 70300240 | TEMPORARY PAVEMENT MARKING LINE 6" | FOOT | 283 | | 283 | |
| 70300260 | TEMPORARY PAVEMENT MARKING LINE 12" | FOOT | 70 | | 70 | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 1462 | 1252 | 210 | |
| *78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 166 | | 166 | |
| *78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 3146 | | 3146 | |
| *78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 283 | | 283 | |
| *78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 70 | | 70 | |
| *78001110 | PAINT PAVEMENT MARKING - LINE 4" | FOOT | 113310 | 104021 | 9289 | |
| 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 594 | 469 | 125 | |
| *78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 10 | 10 | | |
| *78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 4 | 4 | | |
| Z0025500 | FURNISHING AND INSTALLING PROPERTY MARKERS | EACH | 8 | 8 | | |
| | <i>*Specialty Items</i> | | | | | |