

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	JEFFERSON CO.
				RURAL ROADWAY 100% STATE 1000
X0300471	RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT	SO YD	181,278	181,278
X0301424	SILICONE JOINT SEALER	FOOT	168	168
X0322278	RODENT SHIELDS	EACH	247	247
X0322729	MATERIAL TRANSFER DEVICE	TON	110,404	110,404
X0325570	CHANGEABLE MESSAGE SIGN, SPECIAL	CAL DA	42	42
X0325571	TRAFFIC CONTROL SUPERVISOR	CAL DA	42	42
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1
X0325747	BRIDGE DECK CONCRETE CRACK SEALER	FOOT	1,090	1,090
X0326271	SUBGRADE REPAIR	SO YD	3,000	3,000
Z0017202	DOWEL BARS 1 1/2"	EACH	288	288
Z0075310	TIE BARS 3/4"	EACH	288	288
<del>Z0076600</del>	<del>TRAINNEES</del>	<del>HOOR</del>	<del>1,000</del>	<del>1,000</del>
20201006	GRADING AND SHAPING SHOULDERS	UNIT	1,479	1,479
25000200	SEEDING, CLASS 2	ACRE	0.4	0.4
25000350	SEEDING, CLASS 7	ACRE	0.4	0.4
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72	72
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	42	42
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	42	42
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.8	0.8
25100115	MULCH, METHOD 2	ACRE	0.8	0.8
25100630	EROSION CONTROL BLANKET	SO YD	440	440
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	80	80
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	33,713	33,713
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	16,315	16,315
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	26	26
40600895	CONSTRUCTING TEST STRIP	EACH	3	3
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1,280	1,280
40600990	TEMPORARY RAMP	SO YD	1,029	1,029
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	61,973	61,973
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	25,752	25,752
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	22,679	22,679
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	138	138
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	6,720	6,720
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SO YD	15,549	15,549
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	53	53
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SO YD	186,316	186,316

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	JEFFERSON CO.
				RURAL ROADWAY 100% STATE 1000
44000172	HOT-MIX ASPHALT SURFACE REMOVAL, 5 3/4"	SO YD	2,344	2,344
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	199	199
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SO YD	19	19
44213100	PAVEMENT FABRIC	SO YD	19	19
44213200	SAW CUTS	FOOT	1,353	1,353
48203100	HOT-MIX ASPHALT SHOULDERS	TON	42,863	42,863
50104100	BRIDGE HANDRAIL REMOVAL	FOOT	561	561
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	4
50105220	PIPE CULVERT REMOVAL	FOOT	16	16
50300255	CONCRETE SUPERSTRUCTURE	CU YD	16.6	16.6
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3,535.5	3,535.5
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	16	16
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	4	4
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	4	4
54248510	CONCRETE COLLAR	CU YD	3.1	3.1
58700300	CONCRETE SEALER	SO FT	13,608	13,608
60600605	CONCRETE CURB, TYPE B	FOOT	233	233
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	8,922	8,922
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3	3
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	6	6
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	4	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	12	12
63200310	GUARDRAIL REMOVAL	FOOT	14,673	14,673
63500105	DELINEATORS	EACH	288	288
63500120	DELINEATOR REMOVAL	EACH	50	50
64200105	SHOULDER RUMBLE STRIP	FOOT	140,921	140,921
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5
67100100	MOBILIZATION	L SUM	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	4
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	42	42
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	9	9
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5,950	5,950
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1,983	1,983

*\*Specialty Items*

FILE NAME =  
c:\pwwork\pwwid001\SHEPARDD\08172891\78

USER NAME = shepardgd  
76-sht-sched1e.dgn  
PLOT SCALE = 1/8" = 1' IN.  
PLOT DATE = 1/25/2018

DESIGNED -	---	REVISED -	-----
DRAWN -	---	REVISED -	-----
CHECKED -	---	REVISED -	-----
DATE -	---	REVISED -	-----

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: \_\_\_\_\_ SHEET NO. \_\_\_\_ OF \_\_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.I. RTE. 57	SECTION 041-11R-1	COUNTY JEFFERSON	TOTAL SHEETS 47	SHEET NO. 9
CONTRACT NO. 78176			Rev.	

ILLINOIS FED. AID PROJECT