

GUARDRAIL SCHEDULE (SOUTHBOUND)

LOCATION STATION TO STATION	GUARDRAIL REMOVAL FOOT	SPBGR TYPE A FOOT	TRAFFIC BARRIER TERMINAL				GUARDRAIL MARKERS		TERMINAL MARKERS DIRECT APPLIED EACH	CONCRETE CURB, TYPE B FOOT
			TY 1, SPL (TAN) EACH	TYPE 2 EACH	TYPE 6 EACH	TYPE 6B EACH	AMBER EACH	SILVER EACH		
SOUTHBOUND										
LT 309+87.00 TO 313+56.00	369							5		
LT 309+94.00 TO 310+50.25						1		1		
LT 310+50.25 TO 313+06.50		256						4		
LT 313+06.50 TO 313+56.50			1					1	1	
LT 217+74.00 TO 234+28.00	1654							21		38.8
LT 217+42.25 TO 217+92.25			1					1	1	
LT 217+92.25 TO 233+79.75		1588						20		
LT 233+79.75 TO 234+26.00					1			1		
LT 235+55.00 TO 247+52.00	1197							15		38.8
LT 235+59.00 TO 236+05.25					1			1		
LT 236+05.25 TO 247+05.25		1100						14		
LT 247+05.25 TO 247+55.25			1					1	1	
RT 235+55.00 TO 237+10.00	155								2	38.8
RT 235+59.00 TO 236+05.25					1				1	
RT 236+05.25 TO 239+36.50		331							5	
RT 239+36.50 TO 239+86.50			1						1	
LT 163+55.00 TO 170+96.00	741							10		
LT 163+55.00 TO 170+46.00		691		1				9		
LT 170+46.00 TO 170+96.00			1					1	1	
LT 117+00.00 TO 120+22.70	323							5		
LT 117+00.00 TO 117+56.25							1	1		
LT 117+56.25 TO 119+75.00		219						3		
LT 119+75.00 TO 120+25.00			1					1	1	
LT 76+16.00 TO 78+56.00	240							3		
LT 76+00.00 TO 78+87.50		288						4		
LT 78+87.50 TO 79+37.50			1					1	1	
SOUTHBOUND TOTALS:	4,679	4,472	7	1	3	2	123	9	7	116
PROJECT TOTALS:	14,673	8,922	12	3	6	4	134	130	12	233

264

MEDIAN CROSSOVER SCHEDULE

LOCATION STATION	AREA (SQ FT)	INCIDENTAL HMA SURFACING	BITUMINOUS MATERIALS (PRIME COAT)	GRADING AND SHAPING SHOULDERS	TEMPORARY RAMP
		TON	GAL	UNIT	SQ YD
158+37	1625.30	68	23	1	67
370+00	1652.40	69	24	1	67
TOTALS		138	47	2	133