

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES						CODE NO	ITEM	UNIT	TOTAL QUANTITIES					
				<i>1000</i>									<i>1000</i>				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9	9					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	14	14				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	14	14				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	250	250				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	235	235					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	901	901				
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	<i>1,923</i>	<i>1,923</i>					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	4	4				
42101300	PROTECTIVE COAT	SQ YD	<i>76</i>	<i>76</i>					Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	22882	22882													
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1100	1100													
44002218	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4 1/2"	SQ YD	986	986													
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	432	432													
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	160	160													
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	394	394													
55039700	STORM SEWERS TO BE CLEANED	FOOT	250	250													
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	14	14													
60400105	FRAMES, TYPE 1	EACH	5	5													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	303	303													
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	120	120													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9994	9994													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	117	117													
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	150	150													
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110													
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9994	9994													
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	117	117													
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	120	120													

* Specialty Items

FILE NAME =	USER NAME = mitchellr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PARK AVENUE : IL 1 /VINCENNES RD TO 154TH ST	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\k\p\l\dat\mitchellr\1\0137633\0106506\sh-pla.dgn		DRAWN -	REVISED -			3597	163RS	COOK	20	3	
PLOT SCALE = 50,000' / IN.		CHECKED -	REVISED -			SUMMARY OF QUANTITIES					
PLOT DATE = 4/17/2009		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS STA. TO STA.	CONTRACT NO.			
						FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					