

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE ROADWAY 1000						CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE ROADWAY 1000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	16	16						70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
40600300	AGGREGATE (PRIME COAT)	TON	79	79						70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	20	20						70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	35	35					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						70300100	SHORT-TERM PAVEMENT MARKING	FOOT	12410	12410					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1597	1597						70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	401	401					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	160	160						70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11171	11171					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2530	2530						70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1450	1450					
42101300	PROTECTIVE COAT	SQ YD	2090	2090						70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	250	250					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2248	2248						70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	456	456					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	32525	32525						* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	401	401					
44000600	SIDEWALK REMOVAL	SQ FT	2248	2248						* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11171	11171					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	5625	5625						* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3110	3110					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	22	22						* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	250	250					
44200132	PAVEMENT PATCHING, TYPE II, 11 INCH	SQ YD	204	204						* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	456	456					
44200136	PAVEMENT PATCHING, TYPE III, 11 INCH	SQ YD	281	281						* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	189	189					
44200138	PAVEMENT PATCHING, TYPE IV, 11 INCH	SQ YD	679	679						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	139	139					
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	102	102						* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1					
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	140	140						* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1524	1524					
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	339	339						* 87900200	DRILL EXISTING HANDHOLE	EACH	8	8					
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	6	6						* 88500100	INDUCTIVE LOOP DETECTOR	EACH	4	4					
60251730	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	8	8						* 88600100	DETECTOR LOOP, TYPE I	FOOT	132	132					
60254330	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	1	1						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1315	1315					
60255700	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	6	6						* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1200	1200					
60256930	MANHOLES TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	7	7						X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
60258100	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2	2						X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	590	590					
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2						40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	1035	1035					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	4	4						X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2060	2060					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	59	59						X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	2163	2163					
60624600	CORRUGATED MEDIAN	SQ FT	22	22						Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	46	46					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1															

* SPECIALTY ITEMS