

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000						CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	2	2						70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1830	1830					
21400100	GRADING AND SHAPING DITCHES	FOOT	200	200						70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	480	480					
25000210	SEEDING, CLASS 2A	ACRE	0.12	0.12						70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	33845	33845					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	11	11						70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2200	2200					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	11	11						70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1425	1425					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	11	11						70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	350	350					
25100630	EROSION CONTROL BLANKET	SO YD	260	260						70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2125	2125					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	37	37						* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	480	480					
40600300	AGGREGATE (PRIME COAT)	TON	185	185						* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	33845	33845					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	24	24						* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2200	2200					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1425	1425					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	635	635						* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	350	350					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	500	500						* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	450	450					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3880	3880						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	412	412					
42001300	PROTECTIVE COAT	SO YD	70	70						81400115	HANDHOLE TO BE ADJUSTED	EACH	1	1					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	45635	45635						88600600	DETECTOR LOOP REPLACEMENT	FOOT	1145	1145					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	315	315						X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	2955	2955						X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SO YD	25	25					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	4935	4935						X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	1820	1820					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	1465	1465						Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	28	28					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	460	460															
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	540	540															
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	255	255															
55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100															
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	2															
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	17	17															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1															
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1															
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1															

* Specialty Items