

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000 100%STATE						CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000 100%STATE					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	18	18						70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1340	1340					
40600300	AGGREGATE (PRIME COAT)	TON	88	88						70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	600	600					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	13	13						70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1100	1100					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2						* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1150	1150					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	410	410						* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24000	24000					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	606	606						* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3400	3400					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	5200	5200						* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	350	350					
42001300	PROTECTIVE COAT	SQ YD	333	333						* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1340	1340					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	43819	43819						* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	600	600					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1000	1000						* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	840	840					
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	2627	2627						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	791	791					
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	20	20						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1880	1880					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	2140	2140						X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	230	230						X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	20	20					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	210	210						X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	2200	2200					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1						X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1464	1464					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	20	20						Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	113	113					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	50	50						Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1															
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1															
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1															
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10000	10000															
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1150	1150															
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	24000	24000															
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3400	3400															
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	350	350															

* Specialty Items