

SUMMARY OF QUANTITIES			URBAN 1001 STATE	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 1001 STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000'	PARKING LANES				CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000'	PARKING LANES			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	18	16	2				* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5590	5590				
40600300	AGGREGATE (PRIME COAT)	TON	48	42	6				* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2342	2342				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	12	10	2				* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	350	350				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	162	162				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3107	3107					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	250	250				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	201	201					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	250	250				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2000	1750	250				* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	732	732				
42001300	PROTECTIVE COAT	SQ YD	125	125					X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	23806	20828	2978				X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	937	820	117			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	250	250					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	25	25				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1196	1196													
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	500	500													
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	300	300													
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	240	240													
55039700	STORM SEWERS TO BE CLEANED	FOOT	400	400													
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	20	20													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1887	1887													
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	335	335													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5590	5590													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2342	2342													
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	350	350													
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	162	162													
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	210	210													
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	335	335													

*Specialty Items

FILE NAME = c:\pwwork\pwwork\DOT\BANKS\101010534\sh_rdw.dgn	USER NAME = banks	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	1519	2008-032 RS	COOK	21 3
		CHECKED -	REVISED -						CONTRACT NO. 60E72					
		DATE -	REVISED -						FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					