



PROJECT BEGINS
STA. 1+68

MATCHLINE STA. 0+00

W. 63rd Pl.

W. 62ND PLACE

LIMITS OF RESURFACING

IL 171 (Archer Ave.)

63rd Street

S. 76TH AVE.

MATCHLINE STA. 14+00

MATCHLINE STA. 14+00

S. 75TH AVE.

S. 74TH AVE.

63rd Street

MATCHLINE STA. 28+00

PROP. HOT MIX ASPHALT SURFACE REMOVAL (2 1/4") - (TYP.)
 PROP. POLYMERIZED LEVELING BINDER (MM) IL- 4.75, (3/4") - (TYP.)
 PROP. HOT MIX ASPHALT SURFACE COURSE, MIX "D", N70 (1- 1/2") - (TYP.)

NOTES:
 LIMIT OF RESURFACING ON SIDE-STREETS THROUGH OUT THE IMPROVEMENT SHALL BE TO THE RADIUS OF RETURN OR AS DIRECTED BY THE ENGINEER.

ALL FINAL PAVEMENT MARKINGS SHALL BE THERMOPLASTIC (OF THE EXTRUDED TYPE) AND SHOULD BE PLACED IN ACCORDANCE WITH "DISTRICT ONE TYPICAL PAVEMENT MARKINGS" DETAIL, (TC-13).

ALL RAISED REFLECTIVE PAVEMENT MARKINGS SHALL BE PLACED IN ACCORDANCE WITH THE DISTRICT ONE "TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKER DETAIL," (TC-11).

FILE NAME = c:\pwork\pwidot\BANKSL\0110534\sh_r.dgn	USER NAME = banks1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PLAN W. 63rd ST. (ARCHER AVE. TO HARLEM AVE.) ROADWAY AND PAVEMENT MARKING PLAN	F.A.U. RTE. 1519	SECTION 2008-032 RS	COUNTY COOK	TOTAL SHEETS 21	SHEET NO. 7	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	SCALE: 1"=50'			SHEET NO. OF SHEETS	STA. 0+00 TO STA. 28+00	CONTRACT NO. 60E72			
PLOT DATE = 3/25/2009	DATE -	REVISED -						FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			