



CONTROL POINTS ON IL RTE. 83 (OAKTON STREET)

POINT #	STATION	OFFSET	NORTHING	EASTING	DESCRIPTION
1	3+80.27	2.63	10000.0000	10000.0000	X-CUT
2	7+74.25	2.85	10000.0000	10394.0000	X-CUT
4	12+24.12	-33.34	10036.4300	10843.8300	IP
5	20+88.85	-30.78	10034.3500	11708.5600	IR
6	25+89.76	36.64	9967.2100	12209.5100	IP
7	30+81.71	-38.17	10042.2800	12701.4200	IP
8	36+09.56	32.95	9971.4500	13229.3100	IP
9	52+39.64	-37.78	10043.0800	14859.3500	X-CUT
10	52+11.57	70.93	9934.3500	14831.3400	PK NAIL

FILE NAME = #FILES#
PLOT DATE = #DATE#



CHRISTIAN-ROCHE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	K.R.K.	REVISED -	
DRAWN -	B.K.	REVISED -	
CHECKED -	S.J.P.	REVISED -	
DATE -	MARCH 20, 2009	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ALIGNMENT PLAN
IL 83 (OAKTON STREET) IL 72 TO ELMHURST ROAD

SCALE: 1" = 100' SHEET NO. 1 OF 1 SHEETS STA. 0+00 TO STA. 60+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	0405 RS-8	COOK	24	6
CONTRACT NO. 60F41				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				