



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 8, 2009

SUBJECT: FAU Route 3778
Section (3143 & 3144) RS-1
Cook County
Contract No. 60F44
Item No. 12, May 15, 2009 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages i of the Table of Contents to the Special Provisions.
2. Revised pages 2 & 21 of the Special Provisions.
3. Deleted pages 3 - 20 of the Special Provisions.

This Addendum deletes the Special Provision "HOT MIX ASPHALT PAY FOR PERFORMANCE USING PERCENT WITHIN LIMITS (D-1)".

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll, Chief
Bureau of Design and Environment

A handwritten signature in cursive script, appearing to read "Ted B. Walschleger".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Bill Frey, Estimates

TBW:MS:jc

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
MAINTENANCE OF ROADWAYS	1
STATUS OF UTILITIES TO BE ADJUSTED	2
COMPLETION DATE PLUS WORKING DAYS.....	2
HOT MIX ASPHALT MIXTURE IL-4.75 (DISTRICT ONE)	21
HOT MIX ASPHALT MIXTURES, EGA MODIFIED PERFORMANCE GRADED (PG) ASPHALT BINDER	25
COARSE AGGREGATE FOR HOT-MIX ASPHALT (HMA) (D-1)	26
FINE AGGREGATE FOR HOT- MIX ASPHALT (HMA) (D-1)	29
HOT MIX ASPHALT – DENSITY TESTING OF LONGITUDINAL JOINTS (D-1)	29
USE OF RAP (DIST 1).....	30
EPOXY COATING ON REINFORCEMENT (DISTRICT ONE).....	37
TEMPERATURE CONTROL FOR CONCRETE PLACEMENT (DISTRICT ONE)	37
COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	37
CLEANING EXISTING DRAINAGE STRUCTURES	37
FRAMES AND LIDS TO BE ADJUSTED (SPECIAL).....	38
TRAFFIC CONTROL PLAN.....	38
TEMPORARY INFORMATION SIGNING.....	39
TRAFFIC SIGNAL SPECIFICATIONS FOR DETECTOR REPLACEMENT AND/OR INSTALLATION ON ROADWAY GRINDING, RESURFACING, & PATCHING OPERATIONS	40
ALKALI-SILICA REACTION FOR CAST-IN-PLACE CONCRETE (BDE)	43
APPROVAL OF PROPOSED BORROW AREAS, USE AREAS, AND/OR WASTE AREAS INSIDE ILLINOIS STATE BORDERS (BDE)	46
CEMENT (BDE)	46
CONCRETE ADMIXTURES (BDE)	49
CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE).....	52
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	53
ENGINEER’S FIELD OFFICE TYPE A (BDE)	61
EQUIPMENT RENTAL RATES (BDE).....	63
HOT-MIX ASPHALT - FIELD VOIDS IN THE MINERAL AGGREGATE (BDE)	64
HOT-MIX ASPHALT – PLANT TEST FREQUENCY (BDE)	66
HOT-MIX ASPHALT – TRANSPORTATION (BDE)	67
LIQUIDATED DAMAGES (BDE).....	68
MULTILANE PAVEMENT PATCHING (BDE).....	68
NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE)	68

If items of work have not been provided in the contract, or otherwise specified for payment, such items, including the accompanying traffic control and protection required by the Engineer, will be paid for in accordance with Article 109.04 of the Standard Specifications.

STATUS OF UTILITIES TO BE ADJUSTED

Effective: January 30, 1987 Revised: July 1, 1994

Utility companies involved in this project have provided the following estimated dates:

No conflicts are anticipated.

The above represents the best information available to the Department and is included for the convenience of the bidder. The applicable portions of Articles 105.07 and 107.31 of the Standard Specifications shall apply.

COMPLETION DATE PLUS WORKING DAYS

Effective: September 30, 1985 Revised: January 1, 2007

Revise Article 108.05 (b) of the Standard Specifications as follows:

"When a completion date plus working days is specified, the Contractor shall complete all contract items and safely open all roadways to traffic by 11:59 PM on, October 15, 2009 except as specified herein.

The Contractor will be allowed to complete all clean-up work and punch list items within 5 working days after the completion date for opening the roadway to traffic. Under extenuating circumstances the Engineer may direct that certain items of work, not affecting the safe opening of the roadway to traffic, may be completed within the working days allowed for clean up work and punch list items. Temporary lane closures for this work may be allowed at the discretion of the Engineer.

Article 108.09 or the Special Provision for "Failure to Complete the Work on Time", if included in this contract, shall apply to both the completion date and the number of working days.

Pages 3 - 20 have been deleted.
The next page is 21.
Revised 05/08/2009

HOT MIX ASPHALT MIXTURE IL-4.75 (DISTRICT ONE)

Effective: January 1, 2007

Description. This work shall consist of constructing Hot-Mix Asphalt (HMA) surface course or leveling binder with an IL-4.75 mixture. Work shall be according to Sections 406, 1030, 1031 and 1032 of the Standard Specifications except as modified herein.

Revised 05/08/2009