

SUMMARY OF QUANTITIES				URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY		ROADWAY 1000
20200100	EARTH EXCAVATION	CU YD	300		300
20201006	GRADING AND SHAPING SHOULDERS	UNIT	285		285
35800200	AGGREGATE BASE REPAIR	TON	350		350
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	35		35
40600300	AGGREGATE (PRIME COAT)	TON	180		180
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	45		45
40600525	LEVELING BINDER (HAND METHOD), N50	TON	10		10
40600895	CONSTRUCTING TEST STRIP	EACH	2		2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	190		190
40600990	TEMPORARY RAMP	SQ YD	175		175
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	780		780
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	3,900		3,900
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	44,000		44,000
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	4,560		4,560
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	50		50
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	780		780
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	1,050		1,050
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	2,080		2,080
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1,050		1,050
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6		6
67100100	MOBILIZATION	L SUM	1		1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5,000		5,000
• 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	46,500		46,500
• 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	150		150
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5,500		5,500
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	44,700		44,700
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	50		50
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	340		340
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	325		325
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	180		180
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,380		2,380

• DENOTES SPECIALTY ITEM

FILE NAME = \\A:\PROJ\3368\3368_07\Design\ProposedPlan\3368_07_03-Quant.tta.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
6507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = wlancaester	DESIGNED MWR	REVISED -
	DRAWN MWR	REVISED -
PLOT SCALE = 1:8000' / IN.	CHECKED WBL	REVISED -
PLOT DATE = 3/31/2009	DATE 3/31/2009	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL 1
PASADENA AVENUE TO KANKAKEE COUNTY LINE
SUMMARY OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	8 Y-RS-4	WILL	16	3
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 60G35	

SCALE: SHEET NO. 3 OF 16 SHEETS STA. TO STA.