

SUMMARY OF QUANTITIES			1001 STATE 1000	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	5	5
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	20	20
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9,402	9,402
40600300	AGGREGATE (PRIME COAT)	TON	188	188
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	11	11
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	640	640
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3	3
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7,898	7,898
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	24	24
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	20	20
42400800	DETECTABLE WARNINGS	SQ FT	10	10
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	94,024	94,024
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	49	49
44000600	SIDEWALK REMOVAL	SQ FT	20	20
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	858	858
44003100	MEDIAN REMOVAL	SQ FT	1,370	1,370
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	10	10
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	58	58
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	35	35
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	133	133
55039700	STORM SEWERS TO BE CLEANED	FOOT	3,483	3,483
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	3	3
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2
60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	6	6
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	82	82
60404940	FRAMES AND GRATES, TYPE 23	EACH	11	11
60404950	FRAMES AND GRATES, TYPE 24	EACH	11	11
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	11	11

\* SPECIALTY ITEM

SUMMARY OF QUANTITIES			1001 STATE 1000	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	11	11
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	152	152
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	20,400	20,400
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	894	894
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	40,801	40,801
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3,120	3,120
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,285	1,285
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	3,268	3,268
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	825	825
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	894	894
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	40,801	40,801
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3,120	3,120
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,285	1,285
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3,268	3,268
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	825	825
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	808	808
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	155	155
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2,772	2,772
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	308	308
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4,936	4,936
XX002873	BRICK SIDEWALK REMOVAL	SQ FT	38	38
XX004688	BRICK PAVER SIDEWALK	SQ FT	38	38
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	11	11

FILE NAME = ...General\p\In51709sq.dgn	USER NAME = gthiesse	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES US 14 - HICKS ROAD TO VAIL AVENUE</b>	F.A. RTE. 3512	SECTION (88 Y & 88-1YRS-4)	COUNTY COOK	TOTAL SHEETS 22	SHEET NO. 3
	PLOT SCALE = N.T.S.	CHECKED -	REVISED -			CONTRACT NO. 60661				
	PLOT DATE = 4/17/2009	DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
						SCALE:	SHEET NO. OF SHEETS STA. TO STA.			