

URBAN  
100% STATE

SUMMARY OF QUANTITIES		UNIT	TOTAL	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION		QUANTITIES	1000	SFTY-3J
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	50	50	
21400100	GRADING AND SHAPING DITCHES	FOOT	4200	4200	
25000210	SEEDING, CLASS 2A	ACRE	0.41	0.41	
25200100	SODDING	SQ YD	45	45	
25200110	SODDING, SALT TOLERANT	SQ YD	1933	1933	
28101500	RIPRAP, SPECIAL	SQ YD	252	252	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9766	9766	
40600300	AGGREGATE (PRIME COAT)	TON	25	25	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	144	144	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8,203	8,203	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	96,752	96,752	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	900	900	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	726	726	
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	18	18	
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	104	104	
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	105	105	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	2,248	2,248	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,799	2,799	
55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100	
60262700	INLETS TO BE RECONSTRUCTED	EACH	4	4	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1	1	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1	
60400210	FRAMES, TYPE 3	EACH	4	4	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1,338		1,338
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	22		22
63200310	GUARDRAIL REMOVAL	FOOT	963	963	
63500105	DELINEATORS	EACH	38	38	

\* SPECIALTY ITEM

URBAN  
100% STATE

SUMMARY OF QUANTITIES		UNIT	TOTAL	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION		QUANTITIES	1000	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	
67100100	MOBILIZATION	L SUM	1		1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	62,073		62,073
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	186		186
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	124,146		124,146
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,543		1,543
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	605		605
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	794		794
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	12		12
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	186		186
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	124,146		124,146
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,543		1,543
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	605		605
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	794		794
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	12		12
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	950		950
* <del>78200400</del>	<del>GUARDRAIL REFLECTORS</del>	<del>EACH</del>	<del>38</del>		<del>38</del>
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	950		950
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	70		70
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	488		488
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	308		308
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,846		3,846
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1		1
70100400	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1		1

FILE NAME = ...General\p1n51889sq.dgn	USER NAME = gthiesso	DESIGNED - TJJ	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES US 20 - MCHENRY /KANE CD LINE (GETTY ROAD) TO ILL 47</b>		F.A. RTE. 345	SECTION 10 RS-9	COUNTY KANE	TOTAL SHEETS 28	SHEET NO. 3	
PLOT SCALE = N.T.S.		CHECKED - JJT	REVISED -		SCALE: N.T.S.	SHEET NO. 3 OF 28 SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 60G62		
PLOT DATE = 4/17/2009		DATE - 04/16/09	REVISED -									
Rev.												