SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	18	18					
40600300	AGGREGATE (PRIME COAT)	TON	86	86					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	13	13					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	325	325					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	4209	4209					
42001300	PROTECTIVE COAT	SQ YD	70	70					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	42949	42949					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	127	127					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	275	275					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	75	75					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	38	38					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4968	4968					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	803	803					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	12593	12593					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2463	2463					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2647	2647					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	500	500					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	9629	9629					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	803	803					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12593	12593					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2463	2463					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2647	2647					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	500	500					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	552	552					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	469	469					
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	229	229					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1691	1691					
44004600	SIDEWALK REMOVAL AND REPLACEMENT	SQ FT	400	400					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	56	56					

* SPECIALTY ITEMS

FILE NAME = G:\pw_work\PWIDOT\STEEDPA\d0137220\D152209-sht plandgn	USER NAME = lbyss	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES US 52' (JEFFERSON ST.)--JOYCE RD. TO EDEN LN.
	PLOT SCALE = 50.0000 '/ IN.	DRAWN -	REVISED -		
	PLOT DATE = 4/24/2009	CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.
		DATE -	REVISED -		

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
607	128 RS-5	WILL	29	3
		CONTRACT NO. 60G66		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		