

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-2A					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-2A				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	56	56					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	44790	44790				
40600300	AGGREGATE (PRIME COAT)	TON	256	256					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3700	3700				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20					* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	240	240				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	200	200				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	400	400					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	540	540				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5410	5410					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	270	270				
42001300	PROTECTIVE COAT	SO YD	100	100					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	270	270				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	63900	63900					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	360	360				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	300	300					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	102.8	102.8				
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	4394	4394					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2610	2610				
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	105	105													
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	160	160													
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	290	290													
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	700	700													
60260100	INLETS TO BE ADJUSTED	EACH	3	3													
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8	8													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1													
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3300	3300													
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	944	944													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	44790	44790													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3700	3700													
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	240	240													
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	200	200													
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	540	540													
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	944	944													

*Specialty Items

FILE NAME =	USER NAME = gdl/taum/p	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL. RTE. 53 (US 20 (LAKE ST.) TO ARMY TRAIL ROAD) SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLT SCALE = 50,000' / IN.	CHECKED -	REVISED -	870			533 RS-9	DUPAGE	20	3	
PLT DATE = 4/17/2009	DATE -	REVISED -	CONTRACT NO. 60G72			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
			SCALE:			SHEET NO. OF SHEETS	STA. TO STA.			