



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 8, 2009

SUBJECT: FAP Route 541
Section (X-R & T-13-A)RS-1
Lake County
Contract No. 60G78
Item No. 134, May 15, 2009 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages i of the Table of Contents to the Special Provisions.
2. Revised page 14 of the Special Provisions.
3. Deleted pages 15 - 33 of the Special Provisions.

This Addendum deletes the Special Provision "HOT MIX ASPHALT PAY FOR PERFORMANCE USING PERCENT WITHIN LIMITS (D-1)".

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll, Chief
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger" with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Bill Frey, Estimates

TBW:MS:jc

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
MAINTENANCE OF ROADWAYS	1
STATUS OF UTILITIES TO BE ADJUSTED	2
COMPLETION DATE PLUS WORKING DAYS.....	2
FINE AGGREGATE FOR HOT- MIX ASPHALT (HMA) (D-1)	2
USE OF RAP (DIST 1).....	3
HOT MIX ASPHALT – DENSITY TESTING OF LONGITUDINAL JOINTS (D-1)	9
HOT MIX ASPHALT MIXTURE IL-4.75 (DISTRICT ONE)	10
COARSE AGGREGATE FOR HOT-MIX ASPHALT (HMA) (D-1)	34
HOT MIX ASPHALT MIXTURES, EGA MODIFIED PERFORMANCE GRADED (PG) ASPHALT BINDER	37
TEMPERATURE CONTROL FOR CONCRETE PLACEMENT (DISTRICT ONE)	38
EPOXY COATING ON REINFORCEMENT (DISTRICT ONE)	38
COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	38
CLEANING EXISTING DRAINAGE STRUCTURES	39
FRAMES AND LIDS TO BE ADJUSTED (SPECIAL).....	39
TRAFFIC CONTROL PLAN.....	39
TEMPORARY INFORMATION SIGNING.....	40
TRAFFIC SIGNAL SPECIFICATIONS FOR DETECTOR REPLACEMENT AND/OR INSTALLATION ON ROADWAY GRINDING, RESURFACING, & PATCHING OPERATIONS	41
ALKALI-SILICA REACTION FOR CAST-IN-PLACE CONCRETE (BDE)	45
APPROVAL OF PROPOSED BORROW AREAS, USE AREAS, AND/OR WASTE AREAS INSIDE ILLINOIS STATE BORDERS (BDE)	47
CEMENT (BDE)	48
CONCRETE ADMIXTURES (BDE)	50
CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE).....	53
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	54
ENGINEER’S FIELD OFFICE TYPE A (BDE)	62
EQUIPMENT RENTAL RATES (BDE).....	64
HOT-MIX ASPHALT - FIELD VOIDS IN THE MINERAL AGGREGATE (BDE)	65
HOT-MIX ASPHALT – PLANT TEST FREQUENCY (BDE)	67
HOT-MIX ASPHALT – TRANSPORTATION (BDE)	68
LIQUIDATED DAMAGES (BDE).....	69
MULTILANE PAVEMENT PATCHING (BDE).....	69

Revised 05/08/2009

“The compaction operation shall start immediately after the mixture has been placed. The Contractor shall provide a minimum of two steel-wheeled tandem rollers for breakdown (T_B) and one finish steel-wheeled roller (T_F) meeting the requirements of Article 1101.01(e), except the minimum compression for all of the rollers shall be 280 lb/in. (49 N/mm) of roller width. Pneumatic-tired and vibratory rollers will not be permitted.”

Basis of Payment. This work will be paid for at the contract unit price per ton (metric ton) for POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50; and POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-4.75, N50.

Pages 15 - 33 have been Deleted.
The next page is 34.

Revised 05/08/2009