

| SUMMARY OF QUANTITIES | | | 100% STATE | CONSTRUCTION TYPE CODE |
|-----------------------|--|-------|------------------|------------------------|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | 1000 URBAN |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 88 | 88 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 463 | 463 |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 80 | 80 |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | 2 |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 640 | 640 |
| 40601005 | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES | TON | 333 | 333 |
| 40603595 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90 | TON | 11,339 | 11,339 |
| 42001300 | PROTECTIVE COAT | SQ YD | 1,364 | 1,364 |
| 44000159 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2" | SQ YD | 115,700 | 115,700 |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 47 | 47 |
| 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 2,500 | 2,500 |
| 44002214 | HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2" | SQ YD | 1,700 | 1,700 |
| 44003800 | MEDIAN SURFACE REMOVAL | SQ FT | 4,439 | 4,439 |
| 44201753 | CLASS D PATCHES, TYPE II, 9 INCH | SQ YD | 1,000 | 1,000 |
| 44201757 | CLASS D PATCHES, TYPE III, 9 INCH | SQ YD | 500 | 500 |
| 44201759 | CLASS D PATCHES, TYPE IV, 9 INCH | SQ YD | 200 | 200 |
| 55039700 | STORM SEWERS TO BE CLEANED | FOOT | 1,080 | 1,080 |
| 60252800 | CATCH BASINS TO BE RECONSTRUCTED | EACH | 2 | 2 |
| 60257900 | MANHOLES TO BE RECONSTRUCTED | EACH | 2 | 2 |
| 60300305 | FRAMES AND LIDS TO BE ADJUSTED | EACH | 15 | 15 |
| 60300310 | FRAMES AND LIDS TO BE ADJUSTED (SPECIAL) | EACH | 9 | 9 |
| 60404300 | FRAMES AND GRATES, TYPE 3 | EACH | 2 | 2 |
| 60404950 | FRAMES AND GRATES, TYPE 24 | EACH | 2 | 2 |
| 60406100 | FRAMES AND LIDS, TYPE 1, CLOSED LID | EACH | 2 | 2 |
| 60618300 | CONCRETE MEDIAN SURFACE, 4 INCH | SQ FT | 4,327 | 4,327 |
| 60620000 | CONCRETE MEDIAN, TYPE SB-6.24 | SQ FT | 452 | 452 |

| SUMMARY OF QUANTITIES | | | 100% STATE | CONSTRUCTION TYPE CODE |
|-----------------------|--|--------|------------------|------------------------|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | 1000 URBAN |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 6 | 6 |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 |
| 70102630 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701601 | L SUM | 1 | 1 |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 | 1 |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 57,000 | 57,000 |
| 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 2,000 | 2,000 |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 37,000 | 37,000 |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 9,400 | 9,400 |
| 70300250 | TEMPORARY PAVEMENT MARKING - LINE 8" | FOOT | 1,000 | 1,000 |
| 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 1,800 | 1,800 |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 900 | 900 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 17,000 | 17,000 |
| * 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 2,000 | 2,000 |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 37,000 | 37,000 |
| * 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 9,400 | 9,400 |
| * 78000500 | THERMOPLASTIC PAVEMENT MARKING - LINE 8" | FOOT | 1,000 | 1,000 |
| * 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 1,800 | 1,800 |
| * 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 900 | 900 |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 700 | 700 |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 700 | 700 |
| * 88600600 | DETECTOR LOOP REPLACEMENT | FOOT | 6,055 | 6,055 |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 52 | 52 |
| X4067107 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 | TON | 4,859 | 4,859 |
| Z0018500 | DRAINAGE STRUCTURES TO BE CLEANED | EACH | 128 | 128 |

* SPECIALTY ITEM