

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	1000 100% STATE		CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	1000 100% STATE	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	68.4	68.4		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4100	4100	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	56	56		70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	968.4	968.4	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	39204	39204	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	5866	5866		70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1248	1248	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	2284	2284		70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	92	92	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7554	7554		70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	106	106	
42001300	PROTECTIVE COAT	SQ YD	558	558		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1816	1816	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	96056	96056		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	18460	18460	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	300	300		* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	968.4	968.4	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	2913	2913		* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	39204	39204	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1267	1267		* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1248	1248	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	1320	1320		* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	92	92	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	326	326		* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	106	106	
55039700	STORM SEWERS TO BE CLEANED	FOOT	1280	1280		* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1816	1816	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	8	8		* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1611	1611	
60255500	MANHOLES TO BE ADJUSTED	EACH	12	12		X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	528	528	
60260100	INLETS TO BE ADJUSTED	EACH	10	10		X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3778	3778	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	27	27		Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	8	8	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	96	96		Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5							
67100100	MOBILIZATION	L SUM	1	1							
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1							
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1							
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1							
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1							
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4							

*Specialty Items



USER NAME = #USER#	DESIGNED - MJY	REVISIONS
PLOT SCALE = #SCALE#	DRAWN - RJG	REVISIONS
PLOT DATE = #DATE#	CHECKED - MJY	REVISIONS
	DATE - 04/22/2009	REVISIONS

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
COLUMBUS DRIVE

SCALE: NONE	SHEET NO. 3 OF 17 SHEETS	STA. 37+24 TO STA. 37+60	F.A.U. RTE. 3578	SECTION 3178 RS-2	COUNTY COOK	TOTAL SHEETS 27	SHEET NO. 3
			C-91-538-09		CONTRACT NO. 60682		
			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				