

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	32	32
40600300	AGGREGATE (PRIME COAT)	TON	160	160
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	294	294
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	212	212
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3,908	3,908
42001300	PROTECTIVE COAT	SQ YD	130	130
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	39,875	39,875
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	300	300
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	1,080	1,080
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	420	420
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	360	360
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	300	300
55039700	STORM SEWERS TO BE CLEANED	FOOT	1,953	1,953
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	4	4
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	25	25
60404950	FRAMES AND GRATES, TYPE 24	EACH	2	2
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	19,000	19,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	900	900
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	19,469	19,469
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,497	2,497
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	738	738
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	623	623
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,000	3,000
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	900	900
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19,469	19,469
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,497	2,497
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	738	738
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	623	623
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	620	620
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	620	620
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,803	1,803
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	30	30
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,675	1,675
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	68	68
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

* SPECIALTY ITEM

FILE NAME = D168083-shr-S00.dgn
PLOT DATE = 4/15/2009



CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	G.F.L.	REVISED -	
DRAWN -	B.K.	REVISED -	
CHECKED -	M.P.	REVISED -	
DATE -	APRIL 2009	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
ELMHURST ROAD

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2678	3025 RS-2	COOK	17	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
CONTRACT NO. 60683				