

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	33	33					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	592	592					
40600300	AGGREGATE (PRIME COAT)	TON	167	167					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	624	624					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	42	42					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	624	624					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	4707	4707					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	111	111					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	2506	2506					X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SO YD	23	23					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	8187	8187					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3289	3289					
42001300	PROTECTIVE COAT	SO YD	710	710					X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SO YD	16676	16676					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	5120	5120					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	20	20					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2550	2550														
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	69011	69011														
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	291	291														
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	201	201														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6														
67100100	MOBILIZATION	L SUM	1	1														
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1														
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1														
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1														
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4232	4232														
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	508	508														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	46560	46560														
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3923	3923														
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1200	1200														
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	592	592														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1410	1410														
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	46560	46560														
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3932	3932														

* SPECIALTY ITEM