

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
20201006	GRADING AND SHAPING SHOULDERS	UNIT	362	362
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	125	125
40600300	AGGREGATE (PRIME COAT)	TON	620	620
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20
40600535	LEVELING BINDER (HAND METHOD), N70	TON	25	25
40600895	CONSTRUCTING TEST STRIP	EACH	4	4
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,130	1,130
40600990	TEMPORARY RAMP	SQ YD	1,380	1,380
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	13,300	13,300
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	153,600	153,600
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	250	250
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1,600	1,600
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	900	900
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	500	500
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2,210	2,210
55039700	STORM SEWERS TO BE CLEANED	FOOT	2,100	2,100
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5	5
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5	5
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1

• DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	20,100	20,100
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	4,200	4,200
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	224,500	224,500
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	14,400	14,400
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	900	900
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	9,000	9,000
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1,800	1,800
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	33,200	33,200
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,400	1,400
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	136,900	136,900
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4,800	4,800
• 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	300	300
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3,000	3,000
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	600	600
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,360	1,360
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,292	1,292
• 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,050	1,050
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	154	154
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	8,400	8,400
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	30	30
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

FILE NAME = W:\PROJ\3368\3368-22\Design\ProposedPlan\3368-22-03-Quantities.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = aia	DESIGNED - DD	REVISED -
	DRAWN - DD	REVISED -
PLOT SCALE = 1:8000' / IN.	CHECKED - WBL	REVISED -
PLOT DATE = 4/21/2009	DATE - 4/22/09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US 12
IL 31 (TYRON GROVE ROAD) TO LAKE COUNTY LINE
SUMMARY OF QUANTITIES

SCALE: SHEET NO. 3 OF 32 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
334	116 R-RS	MCHENRY	32	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60H22	