

PLOT DATE = 4/20/2009
 FILE NAME = K:\11225514\Rand Road North\Cap\Sheets\RemdNorth_SQU.dgn
 USER NAME = jrb
 MODEL = Default

SUMMARY OF QUANTITIES				
CODE NO.	ITEM DESCRIPTION	UNIT	URBAN	
			100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE I000
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	101	101
40600300	AGGREGATE (PRIME COAT)	TON	505	505
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	21	21
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2782	2782
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	2101	2101
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	16494	16494
42001300	PROTECTIVE COAT	SQ YD	44	44
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	168299	168299
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	9379	9379
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	400	400
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	900	900
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	750	750
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	6500	6500
55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	5	5
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10	10
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2	2
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,257	3,257
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,702	1,702
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	102,350	102,350
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6,638	6,638
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,039	1,039
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	419	419
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,086	1,086
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,702	1,702
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	102,350	102,350

* SPECIALTY ITEM

SUMMARY OF QUANTITIES				
CODE NO.	ITEM DESCRIPTION	UNIT	URBAN	
			100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE I000
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6,638	6,638
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,039	1,039
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	419	419
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	594	594
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	535	535
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,667	1,667
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	7069	7069
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	20	20

* SPECIALTY ITEM



200 West Front Street
 Wheaton, IL 60187

DESIGNED - BLB	REVISED - ---
DRAWN - JMT	REVISED - ---
CHECKED - MAK	REVISED - ---
DATE - 4/20/2009 5:15:34 PM	REVISED - ---

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

US RTE 12 /IL RTE 59
 (RAND ROAD)

SUMMARY OF QUANTITIES

F.A.P. RTE. 334	SECTION OR-RS-3	COUNTY LAKE	TOTAL SHEETS 25	SHEET NO. 3
CONTRACT NO.60H23				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

SCALE: SHEET NO. ___ OF 25 SHEETS STA. _____ TO STA. _____