



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 8, 2009

SUBJECT: FAP Route 347
Section (G & 2)Y-RS-7
DuPage County
Contract No. 60H31
Item No. 204, May 15, 2009 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page i of the Table of Contents to the Special Provisions.
2. Revised pages 12 & 32 of the Special Provisions.
3. Deleted pages 13 - 31 of the Special Provisions.

This Addendum deletes the Special Provision "HOT MIX ASPHALT PAY FOR PERFORMANCE USING PERCENT WITHIN LIMITS (D-1)".

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll, Chief
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger" with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Bill Frey, Estimates

TBW:MS:jc

TABLE OF CONTENTS

LOCATION OF IMPROVEMENT	1
DESCRIPTION OF IMPROVEMENT.....	1
MAINTENANCE OF ROADWAYS.....	1
STATUS OF UTILITIES TO BE ADJUSTED	2
COMPLETION DATE PLUS WORKING DAYS.....	2
DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT.....	2
USE OF RAP (DIST 1).....	3
COARSE AGGREGATE FOR HOT-MIX ASPHALT (HMA) (D-1)	9
FINE AGGREGATE FOR HOT- MIX ASPHALT (HMA) (D-1)	12
HOT MIX ASPHALT – DENSITY TESTING OF LONGITUDINAL JOINTS (D-1)	32
HOT MIX ASPHALT MIXTURE IL-4.75 (DISTRICT ONE)	34
HOT MIX ASPHALT MIXTURES, EGA MODIFIED PERFORMANCE GRADED (PG) ASPHALT BINDER	37
EPOXY COATING ON REINFORCEMENT (DISTRICT ONE)	38
TEMPERATURE CONTROL FOR CONCRETE PLACEMENT (DISTRICT ONE)	38
COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	38
CLEANING EXISTING DRAINAGE STRUCTURES	39
FRAMES AND LIDS TO BE ADJUSTED (SPECIAL).....	39
TRAFFIC CONTROL PLAN.....	39
TEMPORARY INFORMATION SIGNING.....	40
TRAFFIC SIGNAL SPECIFICATIONS FOR DETECTOR REPLACEMENT AND/OR INSTALLATION ON ROADWAY GRINDING, RESURFACING, & PATCHING OPERATIONS	41
ALKALI-SILICA REACTION FOR CAST-IN-PLACE CONCRETE (BDE)	44
APPROVAL OF PROPOSED BORROW AREAS, USE AREAS, AND/OR WASTE AREAS INSIDE ILLINOIS STATE BORDERS (BDE)	47
CEMENT (BDE)	48
CONCRETE ADMIXTURES (BDE)	50
CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE).....	53
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	54
ENGINEER’S FIELD OFFICE TYPE A (BDE)	62
EQUIPMENT RENTAL RATES (BDE).....	64

Revised 05/08/2009

(c) Gradation. The coarse aggregate gradations shall be as listed in the following table.

Use	Size/Application	Gradation No.
Class A-1, 2, & 3	3/8 in. (10 mm) Seal	CA 16
Class A-1	1/2 in. (13 mm) Seal	CA 15
Class A-2 & 3	Cover	CA 14
HMA High ESAL	IL-25.0 IL-19.0 IL-12.5 IL-9.5	CA 7 ^{1/} or CA 8 ^{1/} CA 11 ^{1/} CA 16 and/or CA 13 CA 16
HMA Low ESAL	IL-19.0L IL-9.5L	CA 11 ^{1/} CA 16
HMA All Other	Stabilized Subbase or Shoulders	CA 6 ^{2/} , CA 10, or CA 12

1/ CA 16 or CA 13 may be blended with the gradations listed.

2/ CA 6 will not be permitted in the top lift of shoulders.

FINE AGGREGATE FOR HOT- MIX ASPHALT (HMA) (D-1)

Effective: May 1, 2007

Revised: February 5, 2009

Add the following to the gradation tables of Article 1003.01(c) of the Standard Specifications:

FINE AGGREGATE GRADATIONS					
Grad No.	Sieve Size and Percent Passing				
	3/8	No. 4	No. 8	No. 16	No. 200
FM 23	100	6/	6/	8±8	2±2

FINE AGGREGATE GRADATIONS (metric)					
Grad No.	Sieve Size and Percent Passing				
	9.5 mm	4.75 mm	2.36 mm	1.16 mm	0.075 mm
FM 23	100	6/	6/	8±8	2±2

6/ For the fine aggregate gradations FA 23, the aggregate producer shall set the midpoint percent passing and a range of ± 10% shall be applied. The midpoint shall not be changed without Department approval.

Revise Article 1003.03 (c) of the Standard Specifications to read:

“Gradation. The fine aggregate gradation for all HMA shall be FA1, FA 2, FA 20, FA 21 or FA 23. When Reclaimed Asphalt Pavement (RAP) is incorporated in the HMA design, the use of FA 21 Gradation will not be permitted.

Pages 13 - 31 have been Deleted.
 The next page is 32.
 Revised 05/08/2009

HOT MIX ASPHALT – DENSITY TESTING OF LONGITUDINAL JOINTS (D-1)

Effective: January 1, 2007

Revised: January 8, 2009

Description: This work shall consist of testing the density of longitudinal joints as part of the quality control / quality assurance (QC/QA) of hot-mix asphalt (HMA). This work shall be according to Section 1030 of the Standard Specifications except as follows.

Definitions:

Density Test Location: The station location used for density testing.

Revised 05/08/2009