

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	33	33
40600300	AGGREGATE (PRIME COAT)	TON	151	151
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	685	685
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	399	399
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3,710	3,710
42001300	PROTECTIVE COAT	SQ YD	723	723
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	500	500
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	37,854	37,854
44000600	SIDEWALK REMOVAL	SQ FT	500	500
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2,000	2,000
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	130	130
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	830	830
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	830	830
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	276	276
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	2,376	2,376
55039700	STORM SEWERS TO BE CLEANED	FOOT	1,222	1,222
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	24	24
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	1	1
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1
60404300	FRAMES AND LIDS, TYPE 3	EACH	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN
67100100	MOBILIZATION	L SUM	1	1
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11,920	11,920
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	504	504
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	19,500	19,500
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,108	2,108
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,138	1,138
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	329	329
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	110	110
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	504	504
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19,500	19,500
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,108	2,108
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2,938	2,938
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,138	1,138
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	329	329
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	380	380
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	380	380
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2,005	2,005
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	200	200
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,590	1,590
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	47	47
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

* SPECIALTY ITEM

FILE NAME = 0160H41-sh1-S00.dgn
PLOT DATE = 4/21/2009



CHRISTIAN-RODE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	G.F.L.	REVISED -	
DRAWN -	A.C.S.	REVISED -	
CHECKED -	M.P.	REVISED -	
DATE -	APRIL 20, 2009	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL. RTE. 171 (I-55 TO IL. RTE. 43)

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 12+44 TO STA. 75+19

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
373	2009-053 RS	COOK	20	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				CONTRACT NO. 60H41