

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000- URBAN
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	15
40600300	AGGREGATE (PRIME COAT)	TON	43	43
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	166	166
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	102	102
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	688	688
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	4,954	4,954
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	8,180	8,180
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	520	520
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	280	280
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	120	120
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	120	120
48101200	AGGREGATE SHOULDERS, TYPE B	TON	100	100
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000- URBAN
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10,000	10,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	109	109
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7,435	7,435
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,660	1,660
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	819	819
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	720	720
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	109	109
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7,435	7,435
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,660	1,660
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	819	819
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	121	121
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	121	121
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	344	344
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	4	4

* SPECIALTY ITEM

FILE NAME = D168H42-sht-500.dgn
PLOT DATE = 4/21/2009



CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - G.F.L.	REVISED -
DRAWN - A.C.S.	REVISED -
CHECKED - M.P.	REVISED -
DATE - APRIL 2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL RTE. 171 WEST BOUND CONNECTOR

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 10+00 TO STA. 49+06

F.A.U. RTE. 1549/3569	SECTION BR-RS	COUNTY COOK	TOTAL SHEETS 13	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60H42	