

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	I000 URBAN
20201006	GRADING AND SHAPING SHOULDERS	UNIT	150	150
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	26	26
40600300	AGGREGATE (PRIME COAT)	TON	147	147
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	30	30
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	384	384
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,305	3,305
42001300	PROTECTIVE COAT	SQ YD	20	20
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	75	75
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	5,226	5,226
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	34,119	34,119
44000600	SIDEWALK REMOVAL	SQ FT	75	75
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	50	50
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	50	50
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	260	260
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	50	50
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	50	50
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	50	50
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	720	720
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	425	425
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	370	370
48101200	AGGREGATE SHOULDERS, TYPE B	TON	366	366
55039700	STORM SEWERS TO BE CLEANED	FOOT	180	180
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	I000 URBAN
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	2
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	7	7
60404500	FRAMES AND GRATES, TYPE 6	EACH	1	1
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11,000	11,000
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	47,211	47,211
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	87	87
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	68	68
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	58	58
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,600	1,600
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	47,211	47,211
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	87	87
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	68	68
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	58	58
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	581	581
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	581	581
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,513	1,513
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	33	33

\* SPECIALTY ITEM

FILE NAME = D162381-ahc-500.dgn  
PLOT DATE = 4/1/2009



CHRISTIAN-RODE & ASSOCIATES, INC.  
ENGINEERS-PLANNERS-SURVEYORS  
211 WEST WACKER DRIVE  
CHICAGO, ILLINOIS 60606  
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	G.F.L.	REVISED -	
DRAWN -	B.K.	REVISED -	
CHECKED -	E.J.M.	REVISED -	
DATE -	MARCH 2009	REVISED -	

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
FOREST WAY DRIVE

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 4+45 TO STA. 156+78

C.H.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
92	2002-014 RS	COOK	26	3
			CONTRACT NO. 62381	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				