

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
20201006	GRADING AND SHAPING SHOULDERS	UNIT	1,060	1,060
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	20	20
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	15	15
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	170	170
40600300	AGGREGATE (PRIME COAT)	TON	835	835
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	25	25
40600535	LEVELING BINDER (HAND METHOD), N70	TON	50	50
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,490	1,490
40600990	TEMPORARY RAMP	SQ YD	1,220	1,220
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2	2
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	18,000	18,000
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	207,700	207,700
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	20	20
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	400	400
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	200	200
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	3,200	3,200
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	1,400	1,400
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	2,000	2,000
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	5,860	5,860
55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	15	15
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	3	3
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	3	3

• DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	35,400	35,400
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	840	840
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	186,000	186,000
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3,600	3,600
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,950	1,950
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	780	780
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	22,800	22,800
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	280	280
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	177,500	177,500
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,200	1,200
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	650	650
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	260	260
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,570	1,570
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,500	1,500
88600600	DETECTOR LOOP REPLACEMENT	FOOT	150	150
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	11,300	11,300
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	15	15
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

FILE NAME = N:\PROJ\3368\3368-21\Design\ProcessPlan\3368-21-02-Quantities.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = elau	DESIGNED - EPS	REVISED -
	DRAWN - EPS	REVISED -
PLOT SCALE = 1:8000' / IN.	CHECKED - WBL	REVISED -
PLOT DATE = 4/21/2009	DATE - 4/22/09	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL 173
ALDEN ROAD TO US 12
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 3 OF 36 SHEETS STA. TO STA.

F.A.P. RTE. 303	SECTION (132, 133 & 134) RS-5	COUNTY MCHENRY	TOTAL SHEETS 36	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 62496	