

SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE: 1000-2A					SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE: 1000-2A				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES					CODE NO	ITEM	UNIT	TOTAL QUANTITIES				
				<i>I.000</i>								<i>I.000</i>			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	10				70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	155	155			
40600300	AGGREGATE (PRIME COAT)	TON	47	47				70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4754	4754			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4	4				70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4158	4158			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	336	336			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	234	234				70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	110	110			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	178.4	178.4				70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	197	197			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	987	987				* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	155	155			
42001300	PROTECTIVE COAT	SO YD	128	128				* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4114	4114			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	100	100				* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4158	4158			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	2432	2432				* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	336	336			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	9314	9314				* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	110	110			
44000600	SIDEWALK REMOVAL	SO FT	100	100				* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	165	165			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	350	350				X0322256	TEMPORARY INFORMATION SIGNING	SO FT	102.8	102.8			
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	725	725				X0322748	BICYCLE LANE MARKING	EACH	15	15			
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	230	230				X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	367	367			
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	120	120				Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	11	11			
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	375	375											
55039700	STORM SEWERS TO BE CLEANED	FOOT	200	200											
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	8	8											
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	44	44											
60404940	FRAMES AND GRATES, TYPE 23	EACH	1	1											
60406520	FRAMES AND LIDS, OPEN LID (CITY OF CHICAGO)	EACH	6	6											
60406530	FRAMES AND LIDS, CLOSED LID (CITY OF CHICAGO)	EACH	12	12											
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3											
67100100	MOBILIZATION	L SUM	1	1											
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1											
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1											
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1											
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1070	1070											

* Specialty Items