

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE									
CODE NO	ITEM	UNIT	URBAN 100% STATE		1000	SFTY-2A					CODE NO	ITEM	UNIT	URBAN 100% STATE		1000	SFTY-2A				
			TOTAL QUANTITIES											TOTAL QUANTITIES							
20201006	GRADING AND SHAPING SHOULDERS	UNIT	77		77						70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	37		37						70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10		10					
40600300	AGGREGATE (PRIME COAT)	TON	186		186						70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2545		2545					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	15		15						70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	36.4		36.4					
40600895	CONSTRUCTING TEST STRIP	EACH	3		3						70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	35525		35525					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	727		727						70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	85		85					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	12		12						70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	715		715					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1651		1651						70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	170		170					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3792		3792						70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	285		285					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	4787		4787					*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	36.4		36.4					
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	7337		7337					*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	35525		35525					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	575		575					*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	85		85					
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	39		39					*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	715		715					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	1940		1940					*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	170		170					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	436		436					*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	150		150					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	50		50					*	78200420	GUARDRAIL MARKERS, TYPE B	EACH	10		10					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	89		89					*	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	120		120					
48102100	AGGREGATE <sup>WEDGE</sup> SHOULDER TYPE B	TON	118		118					*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4					
55039700	STORM SEWERS TO BE CLEANED	FOOT	740		740						X0321743	SILICONE JOINT SEALER, 1"	FOOT	245		245					
60255410	CATCH BASINS TO BE CLEANED	EACH	37		37						X0322256	TEMPORARY INFORMATION SIGNING	SO FT	103		103					
60404940	FRAMES AND GRATES, TYPE 23	EACH	9		9						X0323076	SILICONE JOINT SEALER, 1 3/4"	FOOT	134		134					
60404950	FRAMES AND GRATES, TYPE 24	EACH	21		21						X0323077	SILICONE JOINT SEALER, 2 3/4"	FOOT	28		28					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2		2						X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1965		1965					
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	250		250						X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SO YD	2122		2122					
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE C	EACH	3		3						XX001908	PORTLAND CEMENT CONCRETE MEDIAN REMOVAL & REPLACEMENT	SO FT	144		144					
63200310	GUARDRAIL REMOVAL	FOOT	250		250						Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	36		36					
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1, (SPECIAL) FLARED	EACH	5		5						Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5		5					
64200105	SHOULDER RUMBLE STRIP	FOOT	4622		4622						Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	2		2					
63500105	DELINEATORS	EACH	314		314						X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1		1					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6		6																
67100100	MOBILIZATION	L SUM	1		1																
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1		1																
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	5		5																

\* SPECIALTY ITEMS

\* SPECIALTY ITEMS

Rev.