

## NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

| FILE NAME =                           | USER NAME = gorengautab     | DESIGNED - | REVISED - R. MIRS 09-15-97     |                              | ARTERIAL ROAD  | F.A.U. SECTION          | COUNTY TOTAL SHEET |
|---------------------------------------|-----------------------------|------------|--------------------------------|------------------------------|--|-------------------------|--------------------|
| c:\pwwwrk\pwidot\gorengautab\d0139026 | DistStd.dgn                 | DRAWN -    | REVISED - R. MIRS 12-11-97     | STATE OF ILLINOIS            |  | 1301 (0506 & 0607) RS-7 | COOK 19 18         |
|                                       | PLOT SCALE = 50.0000 '/ IN. | CHECKED -  | REVISED -T. RAMMACHER 02-02-99 | DEPARTMENT OF TRANSPORTATION | INFORMATION SIGN                                     | TC-22                   | CONTRACT NO. 62784 |
|                                       | PLOT DATE = 4/21/2009       | DATE -     | REVISED - C. JUCIUS 01-31-07   |                              | SCALE: NONE   SHEET NO. 1 OF 1 SHEETS   STA. TO STA. |                         | AID PROJECT        |