

SUMMARY OF QUANTITIES			
CODE NO.	ITEM	CONSTRUCTION CODE TYPE: I000	
		UNIT	100% STATE I000 TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,262
40600300	AGGREGATE (PRIME COAT)	TON	36
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5
40600525	LEVELING BINDER (HAND METHOD), N50	TON	8
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	657
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,280
40600990	TEMPORARY RAMP	SQ YD	152
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2048
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	108
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	360
42400800	DETECTABLE WARNINGS	SQ FT	240
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	8459
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	15,206
44000600	SIDEWALK REMOVAL	SQ FT	600
48101200	AGGREGATE SHOULDERS, TYPE B	TON	10
56109210	WATER VALVES TO BE ADJUSTED	EACH	12
60255500	MANHOLES TO BE ADJUSTED	EACH	1
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,711
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11,405
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,426
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	190
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11,405
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,426
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	71
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	71

• SPECIALTY ITEMS